





Air Quality Test Report

EPA Compliance Test for Particulate Matter and Lead Emissions

7 Blast Furnace Bldg.
8 Refinery Process Kettles
9 Refinery Bldg.



*Doe Run Company
881 Main Street
Herculaneum, Missouri*



Test Date(s): December 3-5, 2002

MEMPHIS, TENNESSEE - HOUSTON, TEXAS

THE
DOE RUN
COMPANY
Herculaneum Smelting Division
ISO 9002 Certified

Aaron Miller
Environmental Manager
amiller@doerun.com

April 9, 2003

Mr. Bruce Morrison
USEPA Region VII
901 North 5th
Kansas City, KS 66101

Re: Herculaneum Stack Testing


Dear Bruce:

Enclosed you will find our test report of the stack testing conducted in late January. An earlier attempt had been made in December, but due to sampling equipment problems (ice like formations in the sample probe, umbilical cord, and the impinger train) the stack sampling was canceled. The next available date(s) that were mutually agreeable to the agencies and a different stack sampling company (Aeromet) was in late January 2003.

The sample data from the laboratory was not received at Aeromet's offices until late February. During the interim, the Missouri Department of Natural Resources Air Pollution Control Program (MDNR-APCP) requested additional information be added to the sampling report we did for them in 2002. In an effort to produce a report that was more acceptable to MDNR-APCP, the agency that actually oversaw the stack testing in January, it was thought better to understand the information that the MDNR-APCP wanted to see reflected in the stack sampling report rather than produce another report that was lacking in some information that the MDNR-APCP.

We believe that the enclosed report now contains that information to their satisfaction. Should you have any questions concerning the report, please feel free to contact me at your earliest convenience at 636-933-3180.

Sincerely,



Aaron W. Miller
Environmental Manager
Primary Smelting

AWMjlp

cc: Clifton Gray, The Doe Run Company
Doug Elley, MDNR-APCP

881 Main Street, Herculaneum, MO 63048
Telephone: 636-933-3180
Fax: 636-933-3150

RECEIVED

APR 10 2003

SUPERFUND DIVISION

Table of Contents

	<u>Page</u>
Executive Summary.....	1
Introduction.....	2
Summary of Results.....	4
#7 Blast Furnace Bldg. BH.....	4
# 8 Refinery Process Kettles BH.....	5
# 9 Refinery Bldg. BH.....	6
Test Procedures & Specifications.....	7
Calculations.....	11
#7 Blast Furnace Bldg. BH.....	11
# 8 Refinery Process Kettles BH.....	17
# 9 Refinery Bldg. BH.....	23

Appendices

Appendix A - Diagrams

Source Dimensions / Traverse Point Diagram

Sample Train Schematic(s)

Appendix B - Analysis Results (PM/Pb)

Pb Analysis Reports

PM Analysis Reports

Chain of Custody Records

Appendix C - Field Data Records

Appendix D - Equipment Calibrations

Appendix E - Certifications


Appendix F - Related Correspondence

Appendix G - Process Data

Executive Summary

White Star Environmental conducted air quality testing at Doe Run Company, a primary lead smelting plant, located in Herculaneum, Missouri. Three process systems: (1) # 7 Blast Furnace Bldg. baghouse, (2) # 8 Refinery Process Kettles baghouse, and (3) the # 9 Refinery Bldg. baghouse were sampled for particulate matter and lead emissions. The testing was performed during the period December 3-5, 2002 and serves as demonstration of compliance for emissions regulated by EPA and the State of Missouri.

Doe Run Company – Herculaneum, MO
Lead (Pb) Emissions
(lb / 24 hr)



Based on these test results the individual processes designated as the # 8 Refinery Process Kettles, # 9 Refinery Bldg. Baghouse, and the # 7 Blast Furnace Bldg. Baghouse are operating within the specified limits for lead emissions.

Introduction

Doe Run Company, located in Herculaneum, Missouri is operating a primary lead smelting facility, which produces lead from lead sulfide ore concentrates through pyrometallurgical techniques. The Missouri Department of Natural Resources regulates this facility in the quality of air it exhausts to the atmosphere. MDNR Division 10 – Air Conservation Commission establishes the regulatory limitations through CSR 10-6.120.

The *sintering process* is accomplished utilizing a sintering furnace. The lead sulfide ore concentrate charge is heated in the presence of air to eliminate sulfur contained in the charge. The feed material consists of lead concentrate, iron ore, silica sand, limestone, and coke breeze. Metal conveyor belts route the feedstock through the sinter machine where the material ultimately agglomerates into a hard porous mass called sinter.

The *Blast Furnace* is a reduction process to which sinter is charged and forms separate layers of molten slag and lead bullion. The Blast Furnace is charged with feed materials consisting of sinter material and refinery drosses. Lead bullion is tapped continuously into a pot where it is then transferred by crane to the dross kettles. Ventilation hoods located over the pot control emissions from the tapping operations. The slag is tapped into a slag generator where it is palletized by water injection. After de-watering the slag with high lead content is conveyed back to the sintering machine.

As part of the requirements for ensuring air quality compliance, three processes involved in the control of emissions from the production of lead bullion at the facility were sampled for pollutant emissions, (1) # 8 Refinery Process Kettles baghouse, (2) # 9 Refinery Bldg. baghouse, and (3) the # 7 Blast Furnace Bldg. baghouse. The limitations on air pollutants from the facility are provided below.

The #7 baghouse ventilates the combined Blats Furnace and Dross Plant building fugitives. Two blast furnaces are present at the facility. The furnaces are water-jacketed to within 5 feet of the charge floor, and above that, they are lined with refractory. Both are equipped with center line off takes for their process gas streams to a separate #5 baghouse and Main Stack. Emissions from the # 7 Blast Furnace Bldg. Baghouse are controlled using eight Wheelabrator dust collectors in a 8x1 arrangement. This control device is designed to manage 300,000 acfm at full load.

The # 8 baghouse filters air from the kettle hoods in the Refinery and the CV-10 Belt under the Stock Sinter Storage Hoppers. The Refinery is basically a batch process where kettles are worked in batches of roughly 250 tons per batch before moving to another kettle. The emissions related to the # 8 Refinery Process Kettles are controlled using a Wheelabrator Dust Collector arranged in a 5x1 configuration. . This control device is designed to manage 90,000 acfm at full load.

The #9 baghouse ventilates the Refinery building fugitives. Lead is pumped and laundered into the Refining department, which is equipped with eleven 250-ton kettles. Each kettle is heated by one gas-fired burner, which is on a separate ventilation system. Lead is pumped through the sequential kettle series, culminating in delivery of refined lead to casting machines. The emissions related to the # 9 baghouse are controlled using a Wheelabrator Dust Collector arranged in a 5x1 configuration. . This control device is designed to manage 250,000 acfm at full load.

Pollutant emissions from the facility are regulated by the Missouri Department of Natural Resources. The SIP requires lead testing and analysis however the particulate matter testing data were obtained for informational purposes and the results are included herein. Mr. Peter Yronwode, represented the Missouri Department of Natural Resources. The following table provides the applicable limits for each targeted process.

Allowable Limits Summary

Process	Lead (Pb) lbs/24 hours
# 8 Baghouse	8.2
# 7 & # 9 Baghouse (combined)	56.6

White Star Environmental performed the emissions test on the process exhaust stream(s) on December 3-5, 2002. Mr. Scott Postma with the Environmental Protection Agency witnessed the testing.

Test Results Summary

7 Blast Furnace Bldg. Baghouse

Particulate & Lead Emissions Summary December 3, 2002

Test	Particulate Matter (PM)			Lead (Pb)		
	Conc. Gr/dscf	Emission lb/hr	Emission lbs per 24 hr	Conc. Gr/dscf	Emission Lb/hr	Emission lbs per 24 hr
1	0.0029	7.40	177.55	0.00008	0.196	4.71
2	0.0043	11.06	265.00	0.00026	0.680	16.32
3	0.0034	9.02	216.49	0.00024	0.619	14.86
Avg.	0.0035	9.15	219.68	0.00019	0.500	11.96
Limit						56.6

Exhaust Gas Summary

Parameter	Run 1	Run 2	Run 3	Average
Start Time	10:30	12:22	14:46	-
End Time	11:38	13:30	15:54	-
Sample time, min.	60	30	60	60
Gas volume sampled, dscf	44.665	45.093	45.694	45.15
Barometric pressure, in. Hg	29.8	29.8	29.8	29.8
Static pressure, in. H ₂ O	-10.0	-10.0	-10.0	-10.0
Stack pressure, in. Hg	29.06	29.06	29.06	29.06
Gas moisture, %	1.04	1.03	0.92	1.00
Oxygen, %	20.9	20.9	20.9	20.9
Carbon dioxide, %	0.0	0.0	0.0	0.0
Nitrogen, %	79.1	79.1	79.1	79.1
Gas dry mol. wt., lb/lb-mole	28.84	28.84	28.84	28.84
Actual gas mol. wt., lb/lb-mole	28.72	28.72	28.72	28.73
Gas temperature, °F	41	43	42	42
Gas velocity, ft/sec.	51.70	51.92	52.50	52.04
Gas vol. flow, dscf/hr	18,095,546	18,105,763	18,367,994	18,189,763
Isokinetic Variation, %	96.19	97.06	96.95	96.73

Test Results Summary

8 Refinery Process Kettles

Particulate Matter & Lead Emissions December 5, 2002

Test	Particulate Matter (PM)			Lead (Pb)		
	Conc. Gr/dscf	Emission lb/hr	Emission lbs per 24 hr	Conc. Gr/dscf	Emission lb/hr	Emission lbs per 24 hr
1	0.00245	1.724	41.38	0.00047	0.33	7.88
2	0.00378	2.648	63.44	0.00030	0.21	5.05
3	0.00223	1.588	37.98	0.00013	0.10	2.29
Avg.	0.00282	1.983	47.60	0.00030	0.21	5.07
Limit	-	-	-	-	-	8.2

Exhaust Gas Summary

Parameter	Run 1	Run 2	Run 3	Average
Start Time	10:15	11:50	13:50	-
End Time	11:17	12:51	14:51	-
Sample time, min.	60	60	60	60
Gas volume sampled, dscf	39.612	39.891	39.994	39.83
Barometric pressure, in. Hg	30.1	30.1	30.1	30.1
Static pressure, in. H ₂ O	0.20	0.24	0.22	0.22
Stack pressure, in. Hg	30.11	30.12	30.12	30.12
Gas moisture, %	0.47	0.59	0.47	0.51
Oxygen, %	20.9	20.9	20.9	20.9
Carbon dioxide, %	0.0	0.0	0.0	0.0
Nitrogen, %	79.1	79.1	79.1	79.1
Gas dry mol. wt., lb/lb-mole	28.84	28.84	28.84	28.84
Actual gas mol. wt., lb/lb-mole	28.78	28.77	28.79	28.78
Gas temperature, °F	53	57	52	54
Gas velocity, ft/sec.	23.38	23.34	23.45	23.39
Gas vol. flow, dscf/hr	4,927.013	4,900.445	4,960.585	4,926.034
Isokinetic Variation, %	99.53	100.00	99.83	100.12

Test Results Summary

9 Refinery Bldg. Baghouse

Particulate Matter & Lead Emissions December 4, 2002

Test	Particulate Matter (PM)			Lead (Pb)		
	Conc. gr/dscf	Emission lb/hr	Emission lb/hr per day	Conc. gr/dscf	Emission lb/hr	Emission lb/hr per day
1	0.0024	5.09	122.05	0.00149	3.124	74.97
2	0.0029	5.94	142.67	0.00034	0.702	16.85
3	0.0020	4.20	100.72	0.00024	0.493	11.84
Avg.	0.0024	5.08	121.81	0.00069	1.44	34.55
Limit						56.6

Exhaust Gas Summary

Parameter	Run 1	Run 2	Run 3	Average
Start Time	9:48	12:37	14:56	-
End Time	10:56	13:45	16:04	-
Sample time, min.	60	60	60	60
Gas volume sampled, dscf	44.497	44.820	43.570	44.30
Barometric pressure, in. Hg	30.2	30.2	30.2	30.2
Static pressure, in. H ₂ O	-10.0	-10.0	-10.0	-10.0
Stack pressure, in. Hg	29.46	29.46	29.46	29.46
Gas moisture, %	0.74	0.73	0.75	0.74
Oxygen, %	20.9	20.9	20.9	20.9
Carbon dioxide, %	0.0	0.0	0.0	0.0
Nitrogen, %	79.1	79.1	79.1	79.1
Gas dry mol. wt., lb/lb-mole	28.84	28.84	28.84	28.84
Actual gas mol. wt., lb/lb-mole	28.75	28.75	28.75	28.75
Gas temperature, °R	38	36	38	37
Gas velocity, ft/sec.	50.10	49.56	49.66	49.77
Gas vol. flow, dscf/hr	14,693,663	14,590,924	14,581,830	14,622,39
Isokinetic Variation, %	96.41	97.79	95.12	96.45

Test Procedures & Specifications

Determination of Lead Emissions From Stationary Sources EPA REFERENCE METHOD 12 (40 CFR 60, App A)

Forward

The following summary provides discussion of the testing procedures specific to this project. All equipment and methodology adhered to Method 12 requirements unless specified herein. Any deviations from these specifications are noted in bold print. The detailed sampling and analysis procedure is provided in 40 CFR 60, Appendix A.

General

Particulate and gaseous Pb emissions were sampled isokinetically (sample rate equals gas stream linear velocity) from the source and collected on a filter and in dilute nitric acid. The collected samples are digested in acid solution and are analyzed by atomic absorption spectrophotometry using an air/acetylene flame.

Equipment Specifications

A schematic of the sampling train used in performing this method is shown later in this section.

Probe Nozzle – Glass nozzles with a sharp, tapered leading edge were utilized. The angle of taper was 30 degrees and the taper is on the outside to preserve a constant internal diameter. The nozzles were button-hook design.

Probe Liner – Teflon was employed versus using a glass liner. No bias is expected to result from this modification.

Pitot Tube (Type S) - The pitot tube is attached to the probe to allow constant monitoring of the stack gas velocity. The impact (high pressure) opening plane of the pitot tube is even with or above the nozzle entry plane during sampling. The Type S pitot tube assembly was calibrated and assigned a coefficient of 0.84 according to Method 2.

Differential Pressure Gauge – A dual inclined manometer was employed for (1) velocity head (Δp) readings and (2) orifice differential (ΔH) pressure readings. The horizontal scale is 0 - 1 in. H₂O and the vertical scale provided readings in the 1 - 10 in. H₂O range.

Filter Holder & Heating System - A stainless steel in-stack filter device was employed during the procedures. This alteration from the standard practice of using an external heated filter assembly was due to vertical sampling traverses in conjunction with using extensive probe length, which was necessary for the traverse distances. The holder design provides a positive seal against leakage from the outside or around the filter. The holder is attached immediately at the inlet to the probe and is maintained at the stack temperature during sampling.

Metering System - An Apex Instruments Metering Console MC-522 includes a vacuum gauge, pump, dry gas meter (DGM) and related equipment.

Barometer - The barometric pressure reading(s) were obtained from the National Weather Service station located in nearby Farmington, Missouri.

Condensing System - Four impingers connected in series were placed in an ice bath and were utilized to condense moisture vapor and collect pollutant material from the gas stream. The sample train schematic provides a description of these devices.

Reagents and Standards

Filter. Advantec MFS, Inc. thimble filters, 19x90 mm, Grade 86R. A blank filter was submitted to the laboratory for lead analysis with the collected samples.

Water. Deionized distilled, conforms to ASTM D 1193-77 or 91, Type 3.

Acetone. Reagent grade, < 0.001 percent residue, in glass bottles.

Nitric Acid (0.1 N HNO₃), Reagent grade.

Sample Collection

Sampling Train Preparation. The impingers were prepared with 0.1 N HNO₃ in accordance with Method 12 requirements. As the gas stream bubbles through the HNO₃ solution the lead is extracted from the gas stream.

Leak-Check Procedures The sampling train was leak-checked prior to each test run, during changes from ports, and at the conclusion of each test run. The nozzle was plugged and a vacuum higher than encountered during the test was pulled on the system. If the leakage rate is found to be less than 0.020 cfm or 4 percent of the average sampling rate (whichever is less), the results are acceptable and no correction need be applied to the volume of gas metered.

Cyclonic Flow Test The absence of cyclonic flow test was performed on each emission source. The rotation angle was measured at each traverse point and the average value calculated. The sampling location is determined to be free of cyclonic flow if the average rotation angle is less than 20 %. All test values for the sampling locations met this value. The cyclonic flow test data sheets are provided in the appendix section of this report.

Sampling Train Operation The nozzle was placed at each traverse point as identified in the enclosed Source Diagram and the pump rate was set to perform isokinetic sampling. The clock time, sample vacuum, stack gas temperature, DGM volume & temperatures, impinger exit temperature, velocity head (Δp), orifice differential pressure (ΔH) were recorded at each traverse point. During periods of changing ports, the metering system was stopped, leak-checked, and managed in such a manner as to prevent contaminants into the system. The isokinetic percentage of each sampling period was determined to be within the ± 10 % limit.

Sample Recovery Doe Run Company provided laboratory facilities for sample recovery activities. The thimble filter was removed from the holder and sealed in a labeled plastic bag. The impinger contents were measured for volume (ml) gain using a graduated cylinder and then transferred to a 250 ml Qorpak sample bottle labeled "Imp Catch". All system components from the nozzle through the impinger system was rinsed according to Method 12 and collected in a separate 250 ml Qorpak sample bottle labeled "Imp Wash". The silica gel was weighed on-site using a triple beam balance.

Calibration

Equipment calibration records are provided in the Appendix section of this report.

Probe Nozzle. Probe nozzles shall be calibrated before their initial use in the field. Using a micrometer, measure the ID of the nozzle to the nearest 0.025 mm (0.001 in.). Make three separate measurements using different diameters each time, and obtain the average of the measurements. The difference between the high and low numbers shall not exceed 0.1 mm (0.004 in.). When nozzles become nicked, dented, or corroded, they shall be reshaped, sharpened, and recalibrated before use. Each nozzle shall be permanently and uniquely identified.

Pitot Tube Assembly. The Type S pitot-tube assembly shall be calibrated according to the procedure outlined in Method 2.

Metering System. The metering system is calibrated before and after each test project using a wet test meter accurate to within 1 percent. The wet test meter has a capacity of 30 liters/rev (1 ft³/rev). This calibration is performed at each of five orifice manometer settings. The DGM calibration factor, Y, and the orifice calibration factor, $\Delta H_{@}$, are determined and utilized in the emission calculations.

Analytical Procedures

Sample analysis is performed using an atomic absorption spectrophotometer (AAS), which determines the absorbance for each sample. Each sample is analyzed in triplicate and the average value reported. Appropriate dilutions are made, as needed, to bring all sample Pb concentrations into the linear absorbance range of the spectrophotometer. For each source sample, the average absorbance for the contribution of the filter blank and the 0.1 N HNO₃ blank is corrected. Use the calibration curve and this corrected absorbance to determine the Pb concentration in the sample aspirated into the spectrophotometer. Calculate the total Pb content m_1 (in μg) in the original source sample; correct for all the dilutions that were made to bring the Pb concentration of the sample into the linear range of the spectrophotometer. The analysis protocol and chain of custody form submitted with the samples is provided in the Appendix Section of this report.

Method Performance

Precision. The within-laboratory precision, as measured by the coefficient of variation, ranges from 0.2 to 9.5 percent relative to a run-mean concentration. These values were based on tests conducted at a gray iron foundry, a lead storage battery manufacturing plant, a secondary lead smelter, and a lead recovery furnace of an alkyl lead manufacturing plant. The concentrations encountered during these tests ranged from 0.61 to 123.3 mg Pb/m³.

Analytical Range. For a minimum analytical accuracy of ± 10 percent, the lower limit of the range is 100 μg . The upper limit can be extended considerably by dilution.

Analytical Sensitivity. Typical sensitivities for a 1-percent change in absorption (0.0044 absorbance units) are 0.2 and 0.5 $\mu\text{g Pb/ml}$ for the 217.0 and 283.3 nm lines, respectively.

Alternative Procedures (EPA Method 12)

Simultaneous Determination of Particulate and Lead Emissions. Method 5 may be used to simultaneously determine Pb provided: (1) acetone is used to remove particulate from the probe and inside of the filter holder as specified by Method 5, (2) 0.1 N HNO₃ is used in the impingers, (3) a glass fiber filter with a low Pb background is used, and (4) the entire train contents, including the impingers, are treated and analyzed for Pb as described in this method.

Calculations

The following section provides a detailed description of all calculations used in the determination of emission rates. Also listed are all of the intermediate values associated with these calculations.

7 Blast Furnace Bldg. Baghouse

Dry Gas Meter Volume

$$V_{m(std)} = V_m \left[\frac{T_{STD}}{T_m} \right] \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{P_{std}} \right] = 17.64[Y] \left[V_m \right] \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{T_m} \right]$$

Parameter	Run 1	Run 2	Run 3
Vm	42.506	42.88	43.356
Tm	503	502	501
Pbar	29.06	29.06	29.06
ΔH avg	1.85	1.86	1.92
C Factor (Y)	1.036	1.036	1.036
Vm std	44.665	45.093	45.694

Nomenclature

- ΔH = Average pressure drop across orifice, in. H₂O.
- P_{bar} = Barometric pressure, in. Hg.
- T_m = Absolute gas meter temperature, °R
- V_m = Dry gas volume measured, ft³
- Y = Dry gas meter calibration factor
- V_{m(std)} = Dry gas volume corrected to dry, standard conditions, ft³

7 Blast Furnace Bldg. Baghouse

Water Vapor Condensed

$$V_{wcd} = \left[\frac{P_w \cdot R \cdot T_{std}}{M_w \cdot P_{std}} \right] [V_f - V_i] = 0.04707 [V_f - V_i]$$

$$V_{wsgd} = \left[\frac{R \cdot T_{std}}{M_w \cdot P_{std}} \right] [W_f - W_i] = 0.04715 [W_f - W_i]$$

Moisture Content

$$B_{ws} = \left[\frac{V_{wcd} + V_{wsgd}}{V_{wcd} + V_{wsgd} + V_{md}} \right] \cdot 100$$

Parameter	Run 1	Run 2	Run 3
V _{wc}	0.282	0.188	0.235
V _{wsg}	0.189	0.283	0.189
B _{ws} , %	1.04	1.03	0.92

Nomenclature:

- B_{ws} = Water vapor, by volume, in gas stream, %
 ΔH = Average pressure drop across orifice, in. H₂O.
 P_{bar} = Barometric pressure, in. Hg.
 T_m = Absolute gas meter temperature, °R
 V_f, V_i = Impinger system volume, final & initial, ml
 V_m = Dry gas volume measured, ft³
 V_{m(std)} = Dry gas volume corrected to dry, standard conditions, ft³
 V_{wc(std)} = Water vapor condensed, ml
 V_{wsg(std)} = Water vapor captured in silica gel, g
 W_f, W_i = Silica gel weight, final & initial, g
 Y = Dry gas meter calibration factor
 0.04707 = Conversion factor, ft³/ml
 0.04715 = Conversion factor, ft³/g

7 Blast Furnace Bldg. Baghouse

Dry Molecular Weight

$$M_d = 0.44[\%CO_2] + 0.32[\%O_2] + 0.28[\%CO + \%N_2]$$

Molecular Weight of Gas Stream

$$M_s = M_d \cdot \left[\frac{1 - B_{ws}}{100} \right] + 18 \cdot \left[\frac{B_{ws}}{100} \right]$$

Parameter	Run 1	Run 2	Run 3
O ₂ , %	20.9	20.9	20.9
CO ₂ , %	0.0	0.0	0.0
CO + N ₂ , %	79.1	79.1	79.1
B _{ws} , %	1.04	1.03	0.92
M _d , lb/lb-mole	28.84	28.84	28.84
M _s , lb/lb-mole	28.72	28.72	28.74

Nomenclature

- B_{ws} = Water vapor, by volume, in gas stream, %
 M_d = Dry molecular weight of gas stream, lb/lb-mole
 M_s = Molecular weight of gas stream actual conditions, (lb/lb-mole)
 %CO₂ = Carbon dioxide concentration, by volume, %
 %O₂ = Oxygen concentration, by volume, %
 %N₂ = Nitrogen concentration, by volume, %
 %CO = Carbon monoxide concentration, by volume, %
 18 = Molecular weight of H₂O vapor, lb/lb-mole

7 Blast Furnace Bldg. Baghouse

Linear Velocity of Gas Stream

$$V_s = K_p C_p \left[\sqrt{\Delta P} \right]_{avg} \sqrt{\frac{T_s}{P_s M_s}}$$

Parameter	Run 1	Run 2	Run 3
Kp	85.49	85.49	85.49
Cp	0.84	0.84	0.84
SQRT (dP) avg	0.93	0.93	0.94
Ts, R	501	503	502
Ps	29.06	29.06	29.06
Vs	51.70	51.92	52.50

Volumetric Flow Rate of Gas Stream

$$Q_{sd} = 3600 [1 - B_{ws}] V_s A \left[\frac{T_{std}}{T_s} \right] \left[\frac{P_s}{P_{std}} \right]$$

Parameter	Run 1	Run 2	Run 3
Bws, %	1.04	1.03	0.92
As, ft ²	96.00	96.00	96.00
Ts, R	501	503	502
Ps	29.06	29.06	29.06
Qsd, SCFH	18,095,546	18,105,763	18,367,994

Nomenclature

- A = Cross sectional area of gas stream, ft²
 B_{ws} = Water vapor, by volume, in gas stream, %
 C_p = Calibration factor of pitot tube device, dimensionless
 ΔP = Pressure differential of gas stream, in H₂O
 K_p = 85.49 ft/sec[(lb/lb-mole•in. Hg)/(°K•in. H₂O)]^{1/2}
 M_s = Molecular weight of gas stream actual conditions, (lb/lb-mole)
 P_{bar} = Barometric pressure, in. Hg
 P_g = Static pressure of gas stream, in Hg
 P_s = Absolute pressure of gas stream, in. Hg (P_{bar}+P_g)
 P_{std} = Absolute standard pressure, 29.92 in. Hg
 Q_{sd} = Volumetric flow rate of gas stream, dry basis, std cond., ft³/hr
 T_s = Absolute temperature of gas stream, ° R
 T_{std} = Absolute standard temperature, 528° R
 V_s = Linear velocity of gas stream, ft/sec.
 3600 = Conversion factor, sec/hr.

7 Blast Furnace Bldg. Baghouse

Isokinetic Variation

$$I = 100 \cdot T_s \left[\frac{(0.002669) \left\{ V_{ic} + \left(\frac{Y_i \cdot V_m}{T_m} \right) \left(P_{bar} + \frac{\Delta H}{13.6} \right) \right\}}{60 \cdot V_s \cdot P_s \cdot A_n} \right]$$

Parameter	Run 1	Run 2	Run 3
Ts, R	501	503	502
Vic	10	10	9
Yi	1.036	1.036	1.036
Vm	42.506	42.88	43.356
Tm	503	502	501
Pbar	29.06	29.06	29.06
dH avg	1.85	1.86	1.92
sampling time, min.	60	60	60
An	0.00024	0.00024	0.00024
I	96.19	97.06	96.95

Nomenclature

- I = Isokinetic variation, %
 Ts = Absolute temperature of gas stream, °R
 Vic = Water vapor condensed from gas stream, ml
 Y = Dry gas meter calibration factor
 Vm = Dry gas volume measured, ft³
 Tm = Absolute gas meter temperature, °R
 Pbar = Barometric pressure, in. Hg.
 ΔH = Average pressure drop across orifice, in. H₂O.
 13.6 = Inches of water per Hg.
 Vs = Linear velocity of gas stream, ft/sec.
 Ps = Absolute pressure of gas stream, in. Hg (P_{bar}+P_g)
 An = Cross sectional area of nozzle, ft²

7 Blast Furnace Bldg. Baghouse

Pollutant Concentration & Emission Rate

$$C_s, \text{gr/dscf} = (0.0154 \text{ gr/mg})(m_n)/(V_{m \text{ std}})$$

$$E, \text{lb/hr} = (C_s)(Q_{sd})/(7000 \text{ gr/lb})$$

$$E, \text{lb/hr/24 hr} = (E, \text{lb/hr})(24)$$

Particulate Matter

Parameter	Run 1	Run 2	Run 3
m_n , mg	8.3	12.5	10.2
$V_{m \text{ std}}$, dscf	44.665	45.093	45.694
C_s , gr/dscf	0.0029	0.0043	0.0034
Q_{sd} , dscf/hr	18,095,546	18,105,763	18,367,994
E , lb/hr	7.40	11.04	9.02
E , lb/24 hr	177.6	265.0	216.5

Lead (Pb)

Parameter	Run 1	Run 2	Run 3
m_n , mg	0.22	0.77	0.70
$V_{m \text{ std}}$, dscf	44.665	45.093	45.694
C_s , gr/dscf	0.00008	0.00026	0.00024
Q_{sd} , dscf/hr	18,095,546	18,105,763	18,367,994
E , lb/hr	0.196	0.680	0.619
E , lb/24 hr	4.71	16.32	14.86

Nomenclature

- m_n = pollutant material collected, mg or ug
 $V_{m \text{ std}}$ = Dry gas volume corrected to dry, standard conditions, ft³
 C_s , gr/dscf = pollutant concentration, grains per dry standard cubic ft.
 Q_{sd} = Volumetric flow rate of gas stream, dry basis, std cond., ft³/hr
 E , lb/hr = pollutant mass emission rate, pounds per hour
 E , lb/hr/24 hr = pollutant mass emission rate, lb/hr per 24 hour period

Calculations

The following section provides a detailed description of all calculations used in the determination of emission rates for . Also listed are all of the intermediate values associated with these calculations.

8 Refinery Process Kettles

Dry Gas Meter Volume

$$V_{m(std)} = V_m \left[\frac{T_{STD}}{T_m} \right] \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{P_{std}} \right] = 17.64 [Y] V_m \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{T_m} \right]$$

Parameter	Run 1	Run 2	Run 3
Vm	37.404	37.723	37.625
Tm	503	504	501
Pbar	30.1	30.1	30.1
ΔH avg	1.42	1.42	1.43
C Factor (Y)	1.036	1.036	1.036
Vm std	39.612	39.891	39.994

Nomenclature

- ΔH = Average pressure drop across orifice, in. H₂O.
- P_{bar} = Barometric pressure, in. Hg.
- T_m = Absolute gas meter temperature, °R
- V_m = Dry gas volume measured, ft³
- Y = Dry gas meter calibration factor
- V_{m(std)} = Dry gas volume corrected to dry, standard conditions, ft³

8 Refinery Process Kettles

Water Vapor Condensed

$$V_{wcond} = \left[\frac{P_w \cdot R \cdot T_{std}}{M_w \cdot P_{std}} \right] [V_f - V_i] = 0.04707 [V_f - V_i]$$

$$V_{wsgnd} = \left[\frac{R \cdot T_{std}}{M_w \cdot P_{std}} \right] [W_f - W_i] = 0.04715 [W_f - W_i]$$

Moisture Content

$$B_{ws} = \left[\frac{V_{wcond} + V_{wsgnd}}{V_{wcond} + V_{wsgnd} + V_{mnd}} \right] \cdot 100$$

Parameter	Run 1	Run 2	Run 3
V _{wc}	0.047	0.047	0.094
V _{wsg}	0.141	0.189	0.094
B _{ws} , %	0.47	0.59	0.47

Nomenclature:

- B_{ws} = Water vapor, by volume, in gas stream, %
 ΔH = Average pressure drop across orifice, in. H₂O.
 P_{bar} = Barometric pressure, in. Hg.
 T_m = Absolute gas meter temperature, °R
 V_f, V_i = Impinger system volume, final & initial, ml
 V_m = Dry gas volume measured, ft³
 V_{m(std)} = Dry gas volume corrected to dry, standard conditions, ft³
 V_{wc(std)} = Water vapor condensed, ml
 V_{wsg(std)} = Water vapor captured in silica gel, g
 W_f, W_i = Silica gel weight, final & initial, g
 Y = Dry gas meter calibration factor
 0.04707 = Conversion factor, ft³/ml
 0.04715 = Conversion factor, ft³/g

8 Refinery Process Kettles

Dry Molecular Weight

$$M_d = 0.44[\%CO_2] + 0.32[\%O_2] + 0.28[\%CO + \%N_2]$$

Molecular Weight of Gas Stream

$$M_s = M_d \cdot \left[\frac{1 - B_{ws}}{100} \right] + 18 \cdot \left[\frac{B_{ws}}{100} \right]$$

Parameter	Run-1	Run-2	Run-3
O ₂ , %	20.9	20.9	20.9
CO ₂ , %	0.0	0.0	0.0
CO + N ₂ , %	79.1	79.1	79.1
B _{ws} , %	0.47	0.59	0.47
M _d , lb/lb-mole	28.84	28.84	28.84
M _s , lb/lb-mole	28.78	28.77	28.79

Nomenclature

- B_{ws} = Water vapor, by volume, in gas stream, %
 M_d = Dry molecular weight of gas stream, lb/lb-mole
 M_s = Molecular weight of gas stream actual conditions, (lb/lb-mole)
 %CO₂ = Carbon dioxide concentration, by volume, %
 %O₂ = Oxygen concentration, by volume, %
 %N₂ = Nitrogen concentration, by volume, %
 %CO = Carbon monoxide concentration, by volume, %
 18 = Molecular weight of H₂O vapor, lb/lb-mole

8 Refinery Process Kettles

Linear Velocity of Gas Stream

$$V_s = K_p C_p \left[\sqrt{\Delta P} \right]_{\text{avg}} \sqrt{\frac{T_s}{P_s M_s}}$$

Parameter	Run 1	Run 2	Run 3
Kp	85.49	85.49	85.49
Cp	0.84	0.84	0.84
SQRT (dP) avg	0.42	0.42	0.43
Ts, R	513	517	512
Ps	30.11	30.22	30.22
Vs	23.38	23.34	23.45

Volumetric Flow Rate of Gas Stream

$$Q_{sd} = 3600 [1 - B_{ws}] V_s A \left[\frac{T_{std}}{T_s} \right] \left[\frac{P_s}{P_{std}} \right]$$

Parameter	Run 1	Run 2	Run 3
Bws, %	0.47	0.59	0.47
As, ft ²	56.74	56.74	56.74
Ts, R	513	517	512
Ps	30.11	30.22	30.22
Qsd, SCFH	4,927,073	4,890,445	4,960,585

Nomenclature

- A = Cross sectional area of gas stream, ft²
 B_{ws} = Water vapor, by volume, in gas stream, %
 C_p = Calibration factor of pitot tube device, dimensionless
 ΔP = Pressure differential of gas stream, in H₂O
 K_p = 85.49 ft/sec[(lb/lb-mole•in. Hg)/(°K•in. H₂O)]^{1/2}
 M_s = Molecular weight of gas stream actual conditions, (lb/lb-mole)
 P_{bar} = Barometric pressure, in. Hg
 P_g = Static pressure of gas stream, in Hg
 P_s = Absolute pressure of gas stream, in. Hg (P_{bar}+P_g)
 P_{std} = Absolute standard pressure, 29.92 in. Hg
 Q_{sd} = Volumetric flow rate of gas stream, dry basis, std cond., ft³/hr
 T_s = Absolute temperature of gas stream, ° R
 T_{std} = Absolute standard temperature, 528° R
 V_s = Linear velocity of gas stream, ft/sec.
 3600 = Conversion factor, sec/hr.

8 Refinery Process Kettles

Isokinetic Variation

$$I = 100 \cdot T_s \left[\frac{(0.002669) \left[V_{ic} + \left(\frac{Y_i \cdot V_m}{T_m} \right) \left(P_{bar} + \frac{\Delta H}{13.6} \right) \right]}{60 \cdot V_s \cdot P_s \cdot A_n} \right]$$

Parameter	Run 1	Run 2	Run 3
Ts, R	513	517	512
Vic	4	5	4
Yi	1.036	1.036	1.036
Vm	37.404	37.723	37.625
Tm	503	504	501
Pbar	30.1	30.1	30.1
dH avg	1.42	1.42	1.43
sampling time, min.	60	60	60
An	0.000458	0.000458	0.000458
I	99.55	101.00	99.83

Nomenclature

- I = Isokinetic variation, %
 Ts = Absolute temperature of gas stream, °R
 Vic = Water vapor condensed from gas stream, ml
 Yi = Dry gas meter calibration factor
 Vm = Dry gas volume measured, ft³
 Tm = Absolute gas meter temperature, °R
 Pbar = Barometric pressure, in. Hg.
 ΔH = Average pressure drop across orifice, in. H₂O.
 13.6 = Inches of water per Hg.
 Vs = Linear velocity of gas stream, ft/sec.
 Ps = Absolute pressure of gas stream, in. Hg (Pbar + Pg)
 An = Cross sectional area of nozzle, ft²

8 Refinery Process Kettles

Particulate Concentration & Emission Rate

$$C_s, \text{gr/dscf} = (0.0154 \text{ gr/mg})(m_n)/(V_{m \text{ std}})$$

$$E, \text{lb/hr} = (C_s)(Q_{sd})/(7000 \text{ gr/lb})$$

$$E, \text{lb/hr/24 hr} = (E, \text{lb/hr})(24)$$

Particulate Matter

Parameter	Run 1	Run 2	Run 3
m_n , mg	6.3	9.8	5.8
$V_{m \text{ std}}$, dscf	39.612	39.891	39.994
C_s , gr/dscf	0.00245	0.00378	0.00223
Q_{sd} , dscf/hr	4,927,073	4,890,445	4,960,585
E , lb/hr	1.724	2.643	1.583
E , lb/24 hr	41.38	63.44	37.98

Lead (Pb)

Parameter	Run 1	Run 2	Run 3
m_n , mg	1.20	0.78	0.35
$V_{m \text{ std}}$, dscf	39.612	39.891	39.994
C_s , gr/dscf	0.00047	0.00030	0.00013
Q_{sd} , dscf/hr	4,927,073	4,890,445	4,960,585
E , lb/hr	0.328	0.210	0.096
E , lb/24 hr	7.88	5.05	2.92

Nomenclature

- m_n = pollutant material collected, mg or ug
 $V_{m \text{ (std)}}$ = Dry gas volume corrected to dry, standard conditions, ft³
 C_s , gr/dscf = pollutant concentration, grains per dry standard cubic ft.
 Q_{sd} = Volumetric flow rate of gas stream, dry basis, std cond., ft³/hr
 E , lb/hr = pollutant mass emission rate, pounds per hour
 E , lb/hr/24 hr = pollutant mass emission rate, lb/hr per 24 hour period

Calculations

The following section provides a detailed description of all calculations used in the determination of emission rates for . Also listed are all of the intermediate values associated with these calculations.

9 Refinery Bldg. Baghouse

Dry Gas Meter Volume

$$V_{m(std)} = V_m \left[\frac{T_{STD}}{T_m} \right] \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{P_{std}} \right] = 17.64 [Y] V_m \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{T_m} \right]$$

Parameter	Run 1	Run 2	Run 3
V _m	41.653	41.523	40.384
T _m	501	496	496
P _{bar}	30.2	30.2	30.2
ΔH avg	1.77	1.73	1.74
C Factor (Y)	1.036	1.036	1.036
V _{m std}	44.497	44.820	43.570

Nomenclature

- ΔH = Average pressure drop across orifice, in. H₂O.
- P_{bar} = Barometric pressure, in. Hg.
- T_m = Absolute gas meter temperature, °R
- V_m = Dry gas volume measured, ft³
- Y = Dry gas meter calibration factor
- V_{m(std)} = Dry gas volume corrected to dry, standard conditions, ft³

Water Vapor Condensed

$$V_{wcnd} = \left[\frac{P_w \cdot R \cdot T_{std}}{M_w \cdot P_{std}} \right] [V_f - V_i] = 0.04707 [V_f - V_i]$$

$$V_{wsgnd} = \left[\frac{R \cdot T_{std}}{M_w \cdot P_{std}} \right] [W_f - W_i] = 0.04715 [W_f - W_i]$$

Moisture Content

$$B_{ws} = \left[\frac{V_{wcnd} + V_{wsgnd}}{V_{wcnd} + V_{wsgnd} + V_{mnd}} \right] \cdot 100$$

Parameter	Run 1	Run 2	Run 3
V_{wc}	0.141	0.188	0.188
V_{wsg}	0.189	0.141	0.141
Bws, %	0.74	0.73	0.75

Nomenclature:

- B_{ws} = Water vapor, by volume, in gas stream, %
 ΔH = Average pressure drop across orifice, in. H₂O.
 P_{bar} = Barometric pressure, in. Hg.
 T_m = Absolute gas meter temperature, °R
 V_f, V_i = Impinger system volume, final & initial, ml
 V_m = Dry gas volume measured, ft³
 $V_{m(std)}$ = Dry gas volume corrected to dry, standard conditions, ft³
 $V_{wc(std)}$ = Water vapor condensed, ml
 $V_{wsg(std)}$ = Water vapor captured in silica gel, g
 W_f, W_i = Silica gel weight, final & initial, g
 Y = Dry gas meter calibration factor
0.04707 = Conversion factor, ft³/ml
0.04715 = Conversion factor, ft³/g

Dry Molecular Weight

$$M_d = 0.44[\%CO_2] + 0.32[\%O_2] + 0.28[\%CO + \%N_2]$$

Molecular Weight of Gas Stream

$$M_s = M_d \cdot \left[\frac{1 - B_{ws}}{100} \right] + 18 \cdot \left[\frac{B_{ws}}{100} \right]$$

Parameter	Run 1	Run 2	Run 3
O ₂ , %	20.9	20.9	20.9
CO ₂ , %	0.0	0.0	0.0
CO + N ₂ , %	79.1	79.1	79.1
B _{ws} , %	0.74	0.73	0.75
M _d , lb/lb-mole	28.84	28.84	28.84
M _s , lb/lb-mole	28.76	28.76	28.75

Nomenclature

- B_{ws} = Water vapor, by volume, in gas stream, %
 M_d = Dry molecular weight of gas stream, lb/lb-mole
 M_s = Molecular weight of gas stream actual conditions, (lb/lb-mole)
 %CO₂ = Carbon dioxide concentration, by volume, %
 %O₂ = Oxygen concentration, by volume, %
 %N₂ = Nitrogen concentration, by volume, %
 %CO = Carbon monoxide concentration, by volume, %
 18 = Molecular weight of H₂O vapor, lb/lb-mole

Linear Velocity of Gas Stream

$$V_s = K_p C_p \left[\sqrt{\Delta P} \right]_{\text{avg}} \sqrt{\frac{T_s}{P_s M_s}}$$

Parameter	Run 1	Run 2	Run 3
Kp	85.49	85.49	85.49
Cp	0.84	0.84	0.84
SQRT (dP) avg	0.91	0.90	0.90
Ts, R	498	496	498
Ps	29.46	29.46	29.46
Vs	50.10	49.56	49.66

Volumetric Flow Rate of Gas Stream

$$Q_{sd} = 3600 [1 - B_{ws}] V_s A \left[\frac{T_{std}}{T_s} \right] \left[\frac{P_s}{P_{std}} \right]$$

Parameter	Run 1	Run 2	Run 3
Bws, %	0.74	0.73	0.75
As, ft ²	78.67	78.67	78.67
Ts, R	498	496	498
Ps	29.46	29.46	29.46
Qsd, SCFH	14,693,663	14,590,924	14,581,830

Nomenclature

- A = Cross sectional area of gas stream, ft²
 B_{ws} = Water vapor, by volume, in gas stream, %
 C_p = Calibration factor of pitot tube device, dimensionless
 ΔP = Pressure differential of gas stream, in H₂O
 K_p = 85.49 ft/sec[(lb/lb-mole•in. Hg)/(°K•in. H₂O)]^{1/2}
 M_s = Molecular weight of gas stream actual conditions, (lb/lb-mole)
 P_{bar} = Barometric pressure, in. Hg
 P_g = Static pressure of gas stream, in Hg
 P_s = Absolute pressure of gas stream, in. Hg (P_{bar}+P_g)
 P_{std} = Absolute standard pressure, 29.92 in. Hg
 Q_{sd} = Volumetric flow rate of gas stream, dry basis, std cond., ft³/hr
 T_s = Absolute temperature of gas stream, ° R
 T_{std} = Absolute standard temperature, 528° R
 V_s = Linear velocity of gas stream, ft/sec.
 3600 = Conversion factor, sec/hr.

Isokinetic Variation

$$I = 100 \cdot T_s \left[\frac{(0.002669) \left\{ V_{ic} + \left(\frac{Y_i \cdot V_m}{T_m} \right) \left(P_{bar} + \frac{\Delta H}{13.6} \right) \right\}}{60 \cdot \Phi \cdot V_s \cdot P_s \cdot A_n} \right]$$

Parameter	Run 1	Run 2	Run 3
Ts, R	498	496	498
Vic	7	7	7
Yi	1.036	1.036	1.036
Vm	41.653	41.523	40.384
Tm	501	496	496
Pbar	30.2	30.2	30.2
dH avg	1.77	1.73	1.74
sampling time, min.	60	60	60
An	0.00024	0.00024	0.00024
I	99.13	100.56	97.81

Nomenclature

- I = Isokinetic variation, %
 Ts = Absolute temperature of gas stream, ° R
 Vic = Water vapor condensed from gas stream, ml
 Yi = Dry gas meter calibration factor
 Vm = Dry gas volume measured, ft³
 Tm = Absolute gas meter temperature, °R
 Pbar = Barometric pressure, in. Hg.
 ΔH = Average pressure drop across orifice, in. H₂O.
 13.6 = Inches of water per Hg.
 Vs = Linear velocity of gas stream, ft/sec.
 Ps = Absolute pressure of gas stream, in. Hg (P_{bar}+P_g)
 An = Cross sectional area of nozzle, ft²

Pollutant Concentration & Emission Rate

$$C_s, \text{gr/dscf} = (0.0154 \text{ gr/mg})(m_n)/(V_{m \text{ std}})$$

$$E, \text{lb/hr} = (C_s)(Q_{sd})/(7000 \text{ gr/lb})$$

$$E, \text{lb/hr/24 hr} = (E, \text{lb/hr})(24)$$

Particulate Matter

Parameter	Run 1	Run 2	Run 3
m_n , mg	7.000	8.300	5.700
$V_{m \text{ std}}$, dscf	44.497	44.820	43.570
C_s , gr/dscf	0.0024	0.0029	0.0020
Q_{sd} , dscf/hr	14,693,663	14,590,924	14,581,830
E , lb/hr	5.09	5.94	4.20
E , lb/24 hr	122.05	142.67	100.72

Lead (Pb)


Parameter	Run 1	Run 2	Run 3
m_n , mg	4.3	0.98	0.67
$V_{m \text{ std}}$, dscf	44.497	44.820	43.570
C_s , gr/dscf	0.00149	0.00034	0.00024
Q_{sd} , dscf/hr	14,693,663	14,590,924	14,581,830
E , lb/hr	3.12	0.70	0.49
E , lb/24 hr	74.97	16.85	11.84

Nomenclature

- m_n = pollutant material collected, mg or ug
 $V_{m \text{ (std)}}$ = Dry gas volume corrected to dry, standard conditions, ft³
 C_s , gr/dscf = pollutant concentration, grains per dry standard cubic ft.
 Q_{sd} = Volumetric flow rate of gas stream, dry basis, std cond., ft³/hr
 E , lb/hr = pollutant mass emission rate, pounds per hour
 E , lb/hr/24 hr = pollutant mass emission rate, lb/hr per 24 hour period

Appendix A - Diagrams
Source Dimensions / Traverse Point Diagram
Sample Train Schematic(s)

7 Blast Furnace Bldg.



Equivalent Diameter: 115.2 in.


Stack area: 13,824 in² (96 ft²)

	Upstream	Downstream
Distance, in.	84	228
Equiv. Dia.	0.7	2.0
Point	% Diameter	Distance, in.
1	12.5	12.0
2	29.2	28.0
3	45.8	44.0
4	62.5	60.0
5	79.2	76.0
6	95.8	92.0


* Traverse point distance includes a 4 inch port stand-off.

8 Refinery Process Kettles

SIDE VIEW



TOP VIEW




Stack area: 8,171 in² (56.74 ft²)

	Upstream	Downstream
Distance, in.	513	273
Equiv. Dia.	5.0	2.7
Point	% Diameter	Distance, in.
1	3.2	7.3
2	10.5	14.7
3	19.4	23.8
4	32.3	36.9
5	67.7	73.1
6	80.6	86.2
7	89.5	95.3
8	96.8	102.7

* Traverse point distance includes a 4 inch port stand-off.


9 Refinery Bldg.



Equivalent Diameter: 105.9 in.
Stack area: 11,328 in² (78.67 ft²)

	Upstream	Downstream
Distance, in.	84	240
Equiv. Dia.	0.8	2.3
Point	% Diameter	Distance, in.
1	12.5	12.0
2	29.2	28.0
3	45.8	44.0
4	62.5	60.0
5	79.2	76.0
6	95.8	92.0

* Traverse point distance includes a 4 inch port stand-off.



Appendix B - Analysis Results (PM/Pb)

Pb Analysis Reports

PM Analysis Reports

Chain of Custody Records

R E P O R T

White Star Environmental Consulting
ATTN: Mr. Joe Sewell
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70556
Page 1 of 3

Project Description: Four (4) filter and eight (8) impinger sample(s) received on
December 31, 2002
Doe Run Company-Herculaneum Facility
#7 Baghouse
12/3/2002

Dear Mr. Joe Sewell:

Please find enclosed analytical results for the sample(s) submitted to American Interplex Corporation (AIC) on December 31, 2002. The following results are applicable only to samples identified by the control number designated above. Accurate assessment of the data requires access to the entire document. Each section of the report has been reviewed and approved by the appropriate laboratory director or a qualified designee.

If you have any questions, please reference Control No. 70556.

KH/lms

Enclosure(s): Analysis Protocol Form

AMERICAN INTERPLEX CORPORATION

By

John Overbey
Laboratory Director

R E P O R TWhite Star Environmental Consulting
7886 Kirkwood Cove
Olive Branch, MS 38654January 7, 2003
Control No. 70556
Page 2 of 3

ATTN: Mr. Joe Sewell

Project Description: Four (4) filter and eight (8) impinger sample(s) received on
December 31, 2002
Doe Run Company-Herculaneum Facility
#7 Baghouse
12/3/2002Sample Identification: #1927 Run #1, Impinger Catch, Impinger Wash 12/3/02
AIC No. 70556-1

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.22 mg	S9675	02JAN03 0933 201/65

Sample Identification: #1943 Run #2, Impinger Catch, Impinger Wash 12/3/02
AIC No. 70556-2

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.77 mg	S9675	02JAN03 0933 201/65

Sample Identification: #1942 Run #3, Impinger Catch, Impinger Wash 12/3/02
AIC No. 70556-3

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.70 mg	S9675	02JAN03 0933 201/65

Sample Identification: Blank
AIC No. 70556-4

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	<0.004 mg	S9675	02JAN03 0933 201/65



8600 Kanis Road
Little Rock, AR 72204-2322
(501) 224-5060
FAX (501) 224-5072

Q C
R E P O R T

White Star Environmental Consulting
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70556
Page 3 of 3

<u>Parameter</u>	<u>% Recovery</u>	<u>Relative % Difference</u>	<u>Batch</u>
Lead	83.6	1.90	S9675

Data has been validated using standard quality control measures (blank, laboratory control, spike and spike duplicate) performed on at least 10% of samples analyzed. Quality Assurance, instrumentation maintenance and calibration were performed in accordance with guidelines established by the USEPA.
SM method = Standard Methods for the Examination of Water and Wastewater, 20th edition, 1998.

KH/lms



ANALYSIS PROTOCOL

Facility: Doe Run Company – Herculaneum Facility
 Source ID: # 7 Baghouse
 Test Date: 12/3/ 2002

Sample ID	Sample Type	Analysis Req'	Method	A/C
Run #1	Filter # 1927	Lead	12	1
Run #2	Filter # 1943	Lead	12	2
Run #3	Filter # 1942	Lead	12	3
Run #1	Imp Catch	Lead	12	1
Run #2	Imp Catch	Lead	12	2
Run #3	Imp Catch	Lead	12	3
Run #1	HNO ₃ Rinse	Lead	12	1
Run #2	HNO ₃ Rinse	Lead	12	2
Run #3	HNO ₃ Rinse	Lead	12	3
Blank	HNO ₃ Rinse	Lead	12	4
Blank	Filter	Lead	12	4

Composite "Imp Catch" samples with "HNO₃ Rinse" samples by run number.
 Report results in mg or ug.

Please fax results upon completion to Joe Sewell at (662) 895-1651.

Memphis, TN - Houston, TX

Main Office: P.O. Box 238; Olive Branch, MS 38654; (601) 893-3063; Fax: (601) 895-1651

R E P O R T

White Star Environmental Consulting
ATTN: Mr. Joe Sewell
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70559
Page 1 of 3

Project Description: Three (3) filter and six (6) impinger sample(s) received on
December 31, 2002
Doe Run Company-Herculaneum Facility
#8 Baghouse
12/5/2002

Dear Mr. Joe Sewell:

Please find enclosed analytical results for the sample(s) submitted to American Interplex Corporation (AIC) on December 31, 2002. The following results are applicable only to samples identified by the control number designated above. Accurate assessment of the data requires access to the entire document. Each section of the report has been reviewed and approved by the appropriate laboratory director or a qualified designee.

If you have any questions, please reference Control No. 70559.

KH/lms

Enclosure(s): Analysis Protocol Form

AMERICAN INTERPLEX CORPORATION

By

John Overbey
Laboratory Director

R E P O R T

White Star Environmental Consulting
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70559
Page 2 of 3

ATTN: Mr. Joe Sewell

Project Description: Three (3) filter and six (6) impinger sample(s) received on
December 31, 2002
Doe Run Company-Herculaneum Facility
#8 Baghouse
12/5/2002

Sample Identification: 3003 Run #1 Impinger Catch, Impinger Wash 12/5/02
AIC No. 70559-1

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	1.2 mg	S9675	02JAN03 0933 201/65

Sample Identification: 3000 Run #2 Impinger Catch, Impinger Wash 12/5/02
AIC No. 70559-2

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.78 mg	S9675	02JAN03 0933 201/65

Sample Identification: 3002 Run #3 Impinger Catch, Impinger Wash 12/5/02
AIC No. 70559-3

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.35 mg	S9675	02JAN03 0933 201/65

White Star Environmental Consulting
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70559
Page 3 of 3

<u>Parameter</u>	<u>% Recovery</u>	<u>Relative % Difference</u>	<u>Batch</u>
Lead	83.6	1.90	S9675

Data has been validated using standard quality control measures (blank, laboratory control, spike and spike duplicate) performed on at least 10% of samples analyzed. Quality Assurance, instrumentation maintenance and calibration were performed in accordance with guidelines established by the USEPA.
SM method = Standard Methods for the Examination of Water and Wastewater, 20th edition, 1998.

KH/lms

70539



ANALYSIS PROTOCOL

Facility: Doe Run Company – Herculaneum Facility
 Source ID: # 8 Baghouse
 Test Date: 12/5/ 2002

Sample ID	Sample Type	Analysis Req'	Method	A/C
Run #1	Filter # 3003	Lead	12	1
Run #2	Filter # 3000	Lead	12	2
Run #3	Filter # 3002	Lead	12	3
Run #1	Imp Catch	Lead	12	1
Run #2	Imp Catch	Lead	12	2
Run #3	Imp Catch	Lead	12	3
Run #1	HNO ₃ Rinse	Lead	12	1
Run #2	HNO ₃ Rinse	Lead	12	2
Run #3	HNO ₃ Rinse	Lead	12	3
Blank	HNO₃ Rinse	Lead	12	
Blank	Filter	Lead	12	

12/3/02
 1
2
3
4
5
6
7
8
9
10
11
12

Composite "Imp Catch" samples with "HNO₃ Rinse" samples by run number.
 Report results in mg or ug.

Please fax results upon completion to Joe Sewell at (662) 895-1651.

Memphis, TN - Houston, TX

Main Office: P.O. Box 238; Olive Branch, MS 38654; (601) 893-3063; Fax: (601) 895-1651

R E P O R T

White Star Environmental Consulting
ATTN: Mr. Joe Sewell
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70561
Page 1 of 3

Project Description: Three (3) filter and six (6) impinger sample(s) received on
December 31, 2002
Doe Run Company-Herculaneum Facility
#9 Baghouse
12/4/2002

Dear Mr. Joe Sewell:

Please find enclosed analytical results for the sample(s) submitted to American Interplex Corporation (AIC) on December 31, 2002. The following results are applicable only to samples identified by the control number designated above. Accurate assessment of the data requires access to the entire document. Each section of the report has been reviewed and approved by the appropriate laboratory director or a qualified designee.


If you have any questions, please reference Control No. 70561.

KH/lms

Enclosure(s): Analysis Protocol Form

AMERICAN INTERPLEX CORPORATION

By


John Overbey
Laboratory Director

R E P O R T

White Star Environmental Consulting
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70561
Page 2 of 3

ATTN: Mr. Joe Sewell

Project Description: Three (3) filter and six (6) impinger sample(s) received on
December 31, 2002
Doe Run Company-Herculaneum Facility
#9 Baghouse
12/4/2002

Sample Identification: #1931 Run #1 Impinger Catch, Impinger Wash 12/4/02
AIC No. 70561-1

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	4.3 mg	S9675	02JAN03 0933 201/65

Sample Identification: #2003 Run #2 Impinger Catch, Impinger Rinse 12/4/02
AIC No. 70561-2

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.98 mg	S9675	02JAN03 0933 201/65

Sample Identification: #2004 Run #3 Impinger Catch, Impinger Wash 12/4/02
AIC No. 70561-3

<u>Parameter</u>	<u>Method</u>	<u>Result</u>	<u>Batch</u>	<u>Time Analyzed By</u>
Lead	EPA 12	0.67 mg	S9675	02JAN03 0933 201/65



8600 Kanis Road
Little Rock, AR 72204-2322
(501) 224-5060
FAX (501) 224-5072

Q C
R E P O R T

White Star Environmental Consulting
7886 Kirkwood Cove
Olive Branch, MS 38654

January 7, 2003
Control No. 70561
Page 3 of 3

<u>Parameter</u>	<u>% Recovery</u>	<u>Relative % Difference</u>	<u>Batch</u>
Lead	83.6	1.90	S9675

Data has been validated using standard quality control measures (blank, laboratory control, spike and spike duplicate) performed on at least 10% of samples analyzed. Quality Assurance, instrumentation maintenance and calibration were performed in accordance with guidelines established by the USEPA.

SM method = Standard Methods for the Examination of Water and Wastewater, 20th edition, 1998.

KH/lms



ANALYSIS PROTOCOL

Facility: Doe Run Company – Herculaneum Facility
 Source ID: # 9 Baghouse
 Test Date: 12/4/2002

Kw
12/3/02

Sample ID	Sample Type	Analysis Req'	Method	ATC No
Run #1	Filter # 1931	Lead	12	1
Run #2	Filter # 2003	Lead	12	2
Run #3	Filter # 2004	Lead	12	3
Run #1	Imp Catch	Lead	12	1
Run #2	Imp Catch	Lead	12	2
Run #3	Imp Catch	Lead	12	3
Run #1	HNO ₃ Rinse	Lead	12	1
Run #2	HNO ₃ Rinse	Lead	12	2
Run #3	HNO ₃ Rinse	Lead	12	3
Blank	HNO₃ Rinse	Lead	12	
Blank	Filter	Lead	12	

Composite "Imp Catch" samples with "HNO₃ Rinse" samples by run number.
Report results in mg or ug.

Please fax results upon completion to Joe Sewell at (662) 895-1651.

Memphis, TN - Houston, TX

Main Office: P.O. Box 238; Olive Branch, MS 38654; (601) 893-3063; Fax: (601) 895-1651

Gravimetric Analysis Report

Doe Run Company

Herculaneum, MO

#9 Baghouse

Acetone Blank Sample			
Volume, ml	40	<u>Date/Time</u>	
1st weight	35.1089	12/15; 8:00	
2nd weight	35.1089	12/26; 10:00	
Average	35.1089		
Tare Wt.	35.1087		
Blank Wt.	0.0002		
Filter Samples			
Item	Run 1	Run 2	Run 3
Filter No.	1931	2003	2004
1st weight	1.1389	1.243	1.2392
2nd weight	1.1389	1.2433	1.2394
Average	1.1389	1.24315	1.2393
Tare Wt.	1.1342	1.2418	1.2369
Wt. of PM	0.0047	0.00135	0.0024
Acetone Wash Samples			
Item	Run 1	Run 2	Run 3
Volume, ml	50	60	65
1st weight	35.3606	33.4327	35.7543
2nd weight	35.3608	33.433	35.7543
Average	35.3607	33.43285	35.7543
Tare Wt.	35.3581	33.4256	35.7507
Blank Wt.	0.0002	0.0003	0.0003
Wt. of PM	0.0023	0.0069	0.0033
Particulate Matter, mg			
Filter Wt.	4.7	1.3	2.4
Acetone Wt.	2.3	6.9	3.3
Total Wt.	7.0	8.3	5.7

Analyst: WJS

Hygrometer: 40 %

White Star Environmental

Gravimetric Analysis Report

Doe Run Company
Herculaneum, MO
#8 Baghouse

Acetone Blank Sample			
Volume, ml	40	<u>Date/Time</u>	
1st weight	35.1089	12/15; 8:00	
2nd weight	35.1089	12/26; 10:00	
Average	35.1089		
Tare Wt.	35.1087		
Blank Wt.	0.0002		
Filter Samples			
Item	Run 1	Run 2	Run 3
Filter No.	3003	3000	3002
1st weight	1.1639	1.2475	1.2217
2nd weight	1.1639	1.2477	1.2217
Average	1.1639	1.2476	1.2217
Tare Wt.	1.1607	1.2425	1.2201
Wt. of PM	0.0032	0.0051	0.0016
Acetone Wash Samples			
Item	Run 1	Run 2	Run 3
Volume, ml	40	55	55
1st weight	49.4396	36.1486	35.2781
2nd weight	49.4398	36.1487	35.2782
Average	49.4397	36.14865	35.2782
Tare Wt.	49.4364	36.1437	35.2737
Blank Wt.	0.0002	0.0003	0.0003
Wt. of PM	0.0031	0.0047	0.0042
Particulate Matter, mg			
Filter Wt.	3.2	5.1	1.6
Acetone Wt.	3.1	4.7	4.2
Total Wt.	6.3	9.8	5.8

Analyst: WJS

Hygrometer: 40 %

White Star Environmental

Gravimetric Analysis Report

Doe Run Company
Herculaneum, MO
#7 Baghouse

Acetone Blank Sample			
Volume, ml	40	<u>Date/Time</u>	
1st weight	35.1089	12/15; 8:00	
2nd weight	35.1089	12/26; 10:00	
Average	35.1089		
Tare Wt.	35.1087		
Blank Wt.	0.0002		
Filter Samples			
Item	Run 1	Run 2	Run 3
Filter No.	1927	1943	1942
1st weight	1.2769	1.3446	1.3176
2nd weight	1.2769	1.3447	1.3178
Average	1.2769	1.34465	1.3177
Tare Wt.	1.275	1.3363	1.3109
Wt. of PM	0.0019	0.00835	0.0068
Acetone Wash Samples			
Item	Run 1	Run 2	Run 3
Volume, ml	70	60	55
1st weight	53.0244	52.6489	49.1823
2nd weight	53.0244	52.6491	49.1826
Average	53.0244	52.649	49.1825
Tare Wt.	53.0176	52.6446	49.1788
Blank Wt.	0.0003	0.0003	0.0003
Wt. of PM	0.0064	0.0041	0.0034
Particulate Matter, mg			
Filter Wt.	1.9	8.4	6.8
Acetone Wt.	6.4	4.1	3.4
Total Wt.	8.3	12.5	10.2

Analyst: WSP

Hygrometer: 40 %

Appendix C - Field Data Records

Facility Doe Run
 Location Leetown, MO
 Operator TC
 Date 12/3/02
 Run No. 1
 Sample Box No. APEX
 Meter Box No. APEX
 Meter ΔH 1.9
 C Factor 1.5
 Pitot Coeff (C_p) 0.84

#7 Rayhouse
 Diameter (in.) _____
 Downstream (in.) _____
 Upstream (in.) _____

Ambient Temp 33
 Barometric Pressure 29.8 (29.86)
 Diameter 0.21
 Leak Rate (cfm) 0.0015"/11s
 Static Pressure -10.0" H₂O
 Filter No. 1927
 Impinger Vol. (initial) 200
 Impinger Vol. (final) 206
 Silica Gel Wt. (initial) 400
 Silica Gel Wt. (final) 410

Initial Meter Reading: 139.554

Cpts/pt
 2min/point

Traverse Point No.	Sample Time (min.)	Sample Vacuum (in. Hg)	Stack Temp. (°F)	ΔP in. H ₂ O	ΔH in. H ₂ O	Gas Volume (ft ³)	DGM Temp. IN	DGM Temp. OUT	Filter Temp. (°F)	Last Impinger (°F)
1	1037.2	6	34	.65	1.4	140.7	36	36		32
2	1034	6	34	.65	1.4	141.9	37	36		33
3	1036	6	37	.75	1.6	143.2	40	36		36
4	1038	6	38	.75	1.6	144.7	42	36		40
5	1040	6	45	.75	1.6	146.0	44	36		42
6	1042	6	47	.70	1.5	147.2	45	37		43
7	1044	5	41	.60	1.4	148.4	41	37		40
8	1048	6	40	.75	1.6	149.6	44	37		42
9	1050	7	38	.50	1.7	151.0	46	37		43
10	1052	7	41	.70	1.9	152.4	47	37		44
11	1054	7	44	.90	1.9	154.0	49	38		45
12	1056	6	47	.75	1.6	155.3	49	38		45
13	1058	7	40	1.0	2.1	156.8	43	38		41
14	1102	6	39	.80	1.7	158.2	47	38		43
15	1104	6	40	.90	1.9	159.6	48	38		43
16	1106	6	41	.85	1.8	161.0	50	39		44
17	1108	6	43	.85	1.8	162.4	50	39		43
18	1110	6	45	.85	1.8	163.8	51	39		43
19	1112	8	40	1.3	2.7	165.6	45	39		46
20	1114	8	40	1.3	2.7	167.2	49	39		43
21	1116	8	42	1.2	2.6	168.0	51	39		43
22	1120	8	43	1.1	2.3	170.6	51	40		43
23	1122	8	45	1.1	2.3	172.2	52	40		43
24	1124	7	47	1.0	2.1	173.7	52	40		42
25	1128	6	40	.75	1.6	175.0	44	40		40
26	1130	6	38	.80	1.7	176.3	48	40		41
27	1132	6	39	.80	1.7	177.8	49	40		41
28	1134	6	40	.85	1.8	179.2	51	40		41
29	1136	6	42	.90	1.9	180.6	51	40		41
30	1138	6	42	.85	1.8	182.0	51	40		41

Final Meter Reading: _____

182.060

Facility Doc Run
 Location Herrington, MD
 Operator TL
 Date 12/3/02
 Run No. 2
 Sample Box No. Apex
 Meter Box No. Apex
 Meter ΔH 1.5
 C Factor 1.0
 Pitot Coeff (C_p) 0.84

7 Bayphase

Diameter (in.) _____
 Downstream (in.) _____
 Upstream (in.) _____

Ambient Temp 35
 Barometric Pressure 29.8
 Diameter 0.21
 Leak Rate (cfm) 0.00 P15'
 Static Pressure 420 -18.0" H₂O
 Filter No. 1943
 Impinger Vol. (initial) 200
 Impinger Vol. (final) 204
 Silica Gel Wt. (initial) 410
 Silica Gel Wt. (final) 416

Initial Meter Reading: 182.209

Traverse Point No.	Sample Time (min.)	Sample Vacuum (in. Hg)	Stack Temp. (°F)	ΔP in. H ₂ O	ΔH in. H ₂ O	Gas Volume (ft ³)	DGM Temp. IN	DGM Temp. OUT	Filter Temp. (°F)	Last Impinger (°F)
1	1222/24	8	40	1.3	2.7	184.0	37	37		36
2	1226	7	40	1.1	2.3	185.5	37	37		38
3	1228	8	41	1.1	2.3	187.2	39	37		41
4	1230	8	41	1.1	2.3	188.9	41	37		41
5	1232	9	45	1.3	2.7	190.6	42	37		42
6	1234	9	48	1.1	2.3	192.1	43	37		42
7	1236	8	43	1.0	2.1	193.7	41	37		40
8	1240	8	43	1.0	2.1	195.2	44	37		42
9	1242	9	44	1.1	2.3	196.8	45	37		42
10	1244	9	44	1.1	2.3	198.0	47	38		42
11	1246	9	45	1.1	2.3	200.1	48	38		42
12	1248	9	47	1.1	2.3	201.7	49	38		42
13	1250/52	8	41	.85	1.9	203.0	43	38		41
14	1254	8	41	.70	1.5	204.5	46	39		41
15	1256	8	41	.70	1.5	205.6	47	39		41
16	1258	9	43	.85	1.8	207.2	48	39		41
17	1300	9	44	.85	1.8	208.7	49	39		41
18	1302	9	48	.85	1.8	210.5	50	39		41
19	1304/30	6	44	.65	1.4	211.8	43	39		39
20	1308	6	44	.65	1.4	213.0	46	39		41
21	1310	6	40	.70	1.5	214.3	50	40		41
22	1312	7	41	.70	1.5	215.7	49	39		42
23	1314	6	46	.75	1.6	216.4	49	40		42
24	1316	6	46	.75	1.6	217.5	49	40		42
25	1318/1320	7	40	.50	1.1	218.7	43	39		40
26	1322	7	41	.70	1.5	220.0	47	40		41
27	1324	7	41	.65	1.4	221.2	49	40		41
28	1326	7	43	.70	1.5	222.4	50	40		42
29	1328	6	41	.75	1.6	223.7	51	40		42
30	1330	7	42	.75	1.6	225.0	51	40		42

Final Meter Reading: _____

225.089

Facility Doe Run
 Location Hercules, MO
 Operator TC
 Date 12/3/02
 Run No. 3
 Sample Box No. APEX
 Meter Box No. APEX
 Meter ΔH 1.9
 C Factor 1.0
 Pitot Coeff (C_p) 0.84

#7 Bayhouse
 Diameter (in.) _____
 Downstream (in.) _____
 Upstream (in.) _____

Ambient Temp 35
 Barometric Pressure 29.88
 Diameter 0.21
 Leak Rate (cfm) 0.0015" Hg
 Static Pressure -10" H₂O
 Filter No. 1942
 Impinger Vol. (initial) 200
 Impinger Vol. (final) 205
 Silica Gel Wt. (initial) 416
 Silica Gel Wt. (final) 420

Initial Meter Reading: 225.782

Traverse Point No.	Sample Time (min.)	Sample Vacuum (in. Hg)	Stack Temp. (°F)	ΔP in. H ₂ O	ΔH in. H ₂ O	Gas Volume (ft ³)	DGM Temp. IN	DGM Temp. OUT	Filter Temp. (°F)	Last Impinger (°F)
1	1449	7	38	.75	1.6	227.0	36	35		35
2	1450	8	38	1.0	2.1	228.8	37	35		36
3	1452	9	40	1.2	2.6	230.3	40	35		38
4	1454	9	42	1.2	2.6	232.0	42	35		38
5	1456	9	44	1.2	2.6	233.6	42	35		39
6	1458	10	49	1.2	2.6	235.2	43	36		39
7	1500	8	41	1.0	2.1	236.9	39	36		37
8	1502	8	42	1.0	2.1	238.4	43	36		38
9	1504	9	42	1.2	2.6	240.0	43	36		38
10	1506	9	44	1.2	2.6	241.8	47	36		38
11	1508	8	46	1.1	2.3	243.4	48	37		38
12	1510	8	48	1.1	2.3	245.0	48	37		38
13	1512	6	41	.80	1.7	246.4	42	37		37
14	1514	6	38	.80	1.7	247.8	45	37		37
15	1516	6	38	.75	1.6	249.2	47	38		37
16	1518	6	40	.85	1.8	250.6	48	38		37
17	1520	6	43	.85	1.8	251.9	49	38	37	
18	1522	6	48	.85	1.8	253.3	49	38	37	
19	1524	5	40	.60	1.3	254.5	42	38	36	
20	1526	5	39	.60	1.3	255.8	46	38	36	
21	1528	5	38	.65	1.4	257.1	47	38	37	
22	1530	6	41	.85	1.8	258.5	48	38	37	
23	1532	6	45	.85	1.8	259.8	49	38	37	
24	1534	6	48	.85	1.8	261.1	49	38	37	
25	1536	7	41	1.0	2.1	262.7	43	38	36	
26	1538	6	37	.75	1.6	264.1	47	38	37	
27	1540	5	37	.65	1.4	265.2	43	39	36	
28	1542	5	38	.65	1.4	266.5	48	39	37	
29	1544	5	43	.75	1.6	267.8	49	39	37	
30	1546	5	47	.75	1.6	269.1	49	39	37	

Final Meter Reading: _____

269.138

②

Ambient Temp 35
Barometric Pressure 30.1
Diameter 0.29
Leak Rate (cfm) 0.0 @ 10" H₂O
Static Pressure 10.2" H₂O
Filter No. 3003
Impinger Vol. (initial) 200
Impinger Vol. (final) 201
Silica Gel Wt. (initial) 49.4
Silica Gel Wt. (final) 48.7

433.652

Ambient Temp 35
Barometric Pressure 30.1
Diameter 0.79
Leak Rate (cfm) _____
Static Pressure to 24 in H₂O
Filter No. 3000
Impinger Vol. (initial) 200
Impinger Vol. (final) 201
Silica Gel Wt. (initial) 487
Silica Gel Wt. (final) 491

471.65

Ambient Temp 35
Barometric Pressure 30.1
Diameter 0.29
Leak Rate (cfm) 0.0014
Static Pressure 0.27" H₂O
Filter No. 3002
Impinger Vol. (initial) 200
Impinger Vol. (final) 202
Silica Gel Wt. (initial) 454
Silica Gel Wt. (final) 456

Final Meter Reading:

507,477

Facility Doe Run
 Location Hercules, Mo
 Operator TC
 Date 12/4/02
 Run No. 1
 Sample Box No. APEX
 Meter Box No. APEX
 Meter ΔH_0 1.9
 C Factor 1.0
 Pitot Coeff (C_p) 0.94

#9 Bayhorse

Diameter (in.) _____
 Downstream (in.) _____
 Upstream (in.) _____

Ambient Temp 30
 Barometric Pressure 30.2 (29.26)
 Diameter 0.21
 Leak Rate (cfm) 0.0020" Hg
 Static Pressure -10" Hg
 Filter No. 1931
 Impinger Vol. (initial) 200
 Impinger Vol. (final) 203
 Silica Gel Wt. (initial) 430
 Silica Gel Wt. (final) 434

Initial Meter Reading: 269.403

Traverse Point No.	Sample Time (min.)	Sample Vacuum (in. Hg)	Stack Temp. (°F)	ΔP in. H ₂ O	ΔH in. H ₂ O	Gas Volume (ft ³)	DGM Temp. IN	DGM Temp. OUT	Filter Temp. (°F)	Last Impinger (°F)
1	1001.2	6	39	.85	1.8	272.8	35	35		29
2	1002	6	30	.60	1.3	272.1	36	35		29
3	1004	5	32	.55	1.2	273.2	38	35		30
4	1006	6	36	.70	1.5	274.4	39	35		30
5	1008	7	40	.80	1.7	275.6	41	35		31
6	1010	7	47	.85	1.8	277.1	42	35		30
7	1012	5	36	.80	1.7	278.5	39	36		30
8	1014	5	33	.65	1.4	279.7	42	36		31
9	1016	5	34	.75	1.6	281.1	43	36		31
10	1018	5	38	.85	1.8	282.4	45	36		31
11	1020	5	41	.85	1.8	283.9	46	37		32
12	1022	5	48	1.0	2.1	285.4	47	37		32
13	1024	6	38	.65	1.4	286.6	43	37		30
14	1026	6	35	.75	1.6	288.0	45	37		31
15	1028	6	37	.75	1.6	289.3	47	38		32
16	1030	7	40	.85	1.8	290.7	47	37		31
17	1032	8	44	1.0	2.1	292.3	47	38		32
18	1034	9	48	1.2	2.6	293.9	48	38		32
19	1036	6	37	.70	1.5	295.3	41	39		30
20	1038	7	34	.85	1.8	296.6	45	38		31
21	1040	7	35	.85	1.8	298.2	47	38		32
22	1042	8	39	.90	1.9	299.6	47	38		32
23	1044	8	43	1.0	2.1	301.0	49	39		32
24	1046	8	46	1.0	2.1	302.5	49	39		32
25	1048	7	38	.80	1.7	303.8	43	40		31
26	1050	7	33	.75	1.6	305.1	47	40		32
27	1052	7	33	.80	1.7	306.7	47	39		31
28	1054	8	39	.90	1.9	307.9	49	40		32
29	1056	8	44	1.0	2.1	309.5	49	39		32
30	1058	8	43	1.0	2.1	311.0	49	39		32

Final Meter Reading: _____

311.061

Facility Hercules, MO
 Location Doe Run
 Operator TC
 Date 12/4/02
 Run No. 2
 Sample Box No. APEX
 Meter Box No. APEX
 Meter ΔH_a 1.5
 C Factor 1.0
 Pitot Coeff (C_p) 0.84

#9 Baghouse
 Diameter (in.) _____
 Downstream (in.) _____
 Upstream (in.) _____

Ambient Temp 30
 Barometric Pressure 30.2
 Diameter 0.21
 Leak Rate (cfm) 0.0 @ 20" Hg
 Static Pressure -1.5" H₂O
 Filter No. 2003
 Impinger Vol. (initial) 200
 Impinger Vol. (final) 204
 Silica Gel Wt. (initial) 434
 Silica Gel Wt. (final) 437

Initial Meter Reading: 313.657

Traverse Point No.	Sample Time (min.)	Sample Vacuum (in. Hg)	Stack Temp. (°F)	ΔP in. H ₂ O	ΔH in. H ₂ O	Gas Volume (ft ³)	DGM Temp. IN	DGM Temp. OUT	Filter Temp. (°F)	Last Impinger (°F)
1	1241	7	27	.85	1.8	315.0	26	27		23
2	1241	8	26	.75	1.6	316.4	27	26		24
3	1243	9	28	.85	1.8	317.8	30	26		25
4	1245	9	32	.85	1.8	319.1	31	27		25
5	1247	10	37	1.0	2.1	320.6	34	28		26
6	1249	10	40	1.0	2.1	322.1	35	28		27
7	1251/53	10	33	1.1	2.3	323.7	33	29		27
8	1255	9	32	.85	1.8	325.2	36	29		27
9	1257	8	32	.75	1.6	326.5	39	31		29
10	1259	8	33	.75	1.6	327.7	40	31		29
11	1301	8	39	.80	1.7	329.0	41	32		29
12	1303	8	43	.80	1.7	330.4	41	30		29
13	1305/307	8	38	.80	1.7	332.3	38	32		29
14	1309	8	31	.75	1.6	333.6	42	32		29
15	1311	7	32	.65	1.4	334.9	42	32		29
16	1313	8	35	.75	1.6	336.2	43	32		29
17	1315	9	42	.90	1.9	337.6	44	33		29
18	1317	10	45	1.0	2.1	339.0	45	34		29
19	1319/1321	10	39	1.0	2.1	340.7	38	34		29
20	1323	8	36	.70	1.5	341.9	43	34		30
21	1325	8	35	.70	1.5	343.2	44	34		30
22	1327	8	37	.75	1.6	344.5	44	34		30
23	1329	9	43	.90	1.9	345.9	45	34		30
24	1331	10	46	1.0	2.1	347.4	46	35		30
25	1333/35	9	36	.90	1.9	349.1	40	34		30
26	1337	8	33	.70	1.5	350.3	42	34		30
27	1339	7	34	.60	1.3	351.5	43	35		30
28	1341	7	37	.60	1.3	352.6	43	35		30
29	1343	8	44	.70	1.5	353.8	45	35		30
30	1345	8	48	.70	1.5	355.1	45	35		30

Final Meter Reading: _____

355.180

Facility Doe Run
 Location Harcularum, Mo
 Operator TC
 Date 12/4/02
 Run No. 3
 Sample Box No. APEX
 Meter Box No. APEX
 Meter ΔH 1.9
 C Factor 1.0
 Pitot Coeff (C_p) 0.84

49 Bayhouse
 Diameter (in.) _____
 Downstream (in.) _____
 Upstream (in.) _____

Ambient Temp 30
 Barometric Pressure 30.2
 Diameter 0.21
 Leak Rate (cfm) 0.0015" Hg
 Static Pressure -10" H₂O
 Filter No. 2004
 Impinger Vol. (initial) 200
 Impinger Vol. (final) 204
 Silica Gel Wt. (initial) 470
 Silica Gel Wt. (final) 473

Initial Meter Reading: 355.516

Traverse Point No.	Sample Time (min.)	Sample Vacuum (in. Hg)	Stack Temp. (°F)	ΔP in. H ₂ O	ΔH in. H ₂ O	Gas Volume (ft ³)	DGM Temp. IN	DGM Temp. OUT	Filter Temp. (°F)	Last Impinger (°F)
1	1456/58	8	28	.95	2.0	356.7	27	27		27
2	1500	6	29	.70	1.5	358.1	29	28		32
3	1502	6	31	.75	1.6	359.3	30	28		34
4	1504	8	34	.90	1.9	360.8	33	30		35
5	1506	8	41	1.0	2.1	362.3	35	28		35
6	1508	8	45	1.1	2.3	363.9	37	29		37
7	1510/512	7	36	.85	1.8	365.1	35	30		35
8	1514	5	34	.75	1.6	366.5	37	30		36
9	1516	6	33	.80	1.7	367.9	39	30		36
10	1518	6	35	.90	1.9	369.3	40	30		36
11	1520	7	41	1.0	2.1	370.8	42	31		36
12	1522	8	46	1.1	2.3	372.4	43	32		37
13	1524/526	6	35	.80	1.7	373.8	36	32		33
14	1528	5	32	.65	1.4	375.0	40	32		36
15	1530	5	33	.65	1.4	376.3	41	32		36
16	1532	6	37	.86	1.7	377.6	43	32		36
17	1534	6	40	.85	1.8	379.0	44	32		36
18	1536	7	43	.95	2.0	380.5	45	33		36
19	1538/540	7	38	.90	1.9	382.0	38	33		34
20	1542	6	33	.80	1.7	383.3	44	33		36
21	1544	6	32	.70	1.5	384.6	44	33		35
22	1546	6	36	.80	1.7	386.0	45	34		36
23	1548	6	42	.80	1.7	387.4	46	34		36
24	1550	6	47	.90	1.9	388.8	46	34		36
25	1552/54	7	39	1.0	2.1	390.5	39	34		34
26	1556	6	36	.70	1.5	391.8	44	34		35
27	1558	5	37	.55	1.2	392.9	44	35		36
28	1600	7	41	.65	1.4	393.4	45	35		36
29	1602	7	47	.65	1.4	394.6	45	34		36
30	1604	7	48	.65	1.4	395.9	45	34		36

Final Meter Reading: 395.900

Appendix D - Equipment Calibrations

Dry Gas Meter Calibration Form

Certification Date: 1/10/2003

Pb (in.Hg): 30

Meter Box I.D.: Apex

Orifice Manometer Setting, dH, in.H ₂ O	Wet Test Meter Volume V _w , ft ³	Dry Gas Meter Volume V _m , ft ³	Temperatures				Time Theta, min.
			Wet Test Meter t _w , F	DGM Inlet t _i , F	DGM Outlet t _o , F	DGM Average t _m , F	
0.5	10.00	9.818	48.0	56.3	50.7	53.5	25.50
1.0	10.00	9.803	48.0	63.0	51.0	57.0	18.25
2.0	10.00	9.786	48.0	67.3	53.3	60.3	13.75
3.0	10.00	9.814	48.0	67.7	54.7	61.2	10.75
3.5	10.00	9.835	48.0	69.7	56.0	62.8	9.75

Orifice Manometer Setting, dH, in.H ₂ O	Calibration Factor, Y	Orifice Pressure Differential, dH@
0.5	1.028	1.736
1.0	1.036	1.777
2.0	1.042	2.009
3.0	1.038	1.837
3.5	1.038	1.758
Average:	1.036	1.823
Standard Deviation	0.005	0.110
Acceptable Value?	YES!	YES!

*Tolerances for individual Y values +/- 0.02 from average.

**Tolerances for individual dH@ values +/- 0.20 from average.

$$Y = \frac{V_w P_b (t_m + 460)}{V_m \left[P_b + \frac{dH}{13.6} \right] (t_w + 460)}$$

$$dH@ = \frac{0.0317 dH}{P_b (t_o + 460)} \left[\frac{(t_w + 460) \Theta}{V_w} \right]^2$$




Figure 2-7. Proper thermocouple placement to prevent interference;
 D_t between 0.48 and 0.95 cm (3/16 and 3/8 in.).




Figure 2-8. Minimum pitot-sample probe separation needed to prevent interference;
 D_t between 0.48 and 0.95 cm (3/16 and 3/8 in.).

White Star Environmental Pitot Assembly Calibration Data

Pitot Assembly #: thimble filter assembly

$W = 6.035"$

$Z = 2.195"$

$Y = 11.559"$

Appendix E - Certifications
Certification
Personnel Qualifications

CERTIFICATION

White Star Environmental Consulting Corporation (WSECC) performed air quality testing at Doe Run Company located in Herculaneum, Missouri on December 3-5, 2002. Three process systems: (1) # 7 Blast Furnace Bldg. baghouse, (2) # 8 Refinery Process Kettles baghouse, and (3) the # 9 Refinery Bldg. baghouse were sampled for particulate matter and lead emissions.

Air quality testing services performed by White Star Environmental pursuant to the terms of the agreement are provided by adhering to sampling and analysis procedures as established by the Environmental Protection Agency in the Code of Federal Regulations, 40 CFR Part 60. No unapproved deviation or alternative procedure was employed during these exercises and the results are considered to be accurate and representative.



William J. Sewell, II
White Star Environmental - President



Timothy Carey
White Star Environmental - Field Supervisor

January 15, 2003

Date

William J. Sewell, II
President

Summary of Professional Experience

White Star Environmental Consulting Corporation

Position: President

Professional environmental consultant servicing industrial facilities with air pollution related projects including permitting, compliance testing, CEM systems & certifications, etc. Providing air pollution sampling and analysis expertise for industry. Responsible for technical development of Title V permit applications and QA/QC technical documents for EPA compliance on CEMS applications. (1995 – present)

Ramcon Environmental Corporation

Position: Vice President

Responsibilities include management of corporate operations providing EPA regulatory compliance services. Responsibilities include administration and management of professional staff, EPA regulatory adviser, technical writing, generation of new business opportunities, development of services division, QA/QC program & safety management program (1988 - 1995)

Education

B.S. in Chemical Engineering

Christian Brothers University, May 1986

M.S. in Engineering Management

Christian Brothers University, May 1997

Accomplishments, Skills, & Affiliations

- Twelve years of air quality testing project management experience. Projects include air emission testing from boilers, incinerators, furnaces, turbines, etc.
- Member Arkansas Environmental Federation & Air Committee Member.
- Expertise in EPA Title 40 regulations.
- 1990 Clean Air Amendments (CAAA) regulatory specialist (Acid Rain Program, HAPS, Permitting).
- Development of Neural Network Predictive Emissions Monitoring Systems (PEMS) sampling and data collection protocol. Received recognition from national publications for active participation.
- Training seminar for Arkansas Dept. of Environmental Quality on compliance test observation techniques.

Timothy Ryan Carey
Vice President

Summary of Professional Experience

White Star Environmental Consulting Corporation

Position: Vice President

Professional environmental consultant servicing industrial facilities with air pollution related projects including compliance testing, CEM systems & certifications, etc. Providing air pollution sampling and analysis expertise for industry.

(1997 – present)

Ramcon Environmental Corporation

Position: Project Engineer

Professional environmental consultant servicing industrial facilities with air pollution related projects including compliance testing, CEM systems & certifications, etc. Providing air pollution sampling and analysis expertise for industry.

(1995 - 1997)

Education

B.S. in Mechanical Engineering

University of Arkansas, May 1994

Accomplishments, Skills, & Affiliations

- Seven years of air quality testing project management experience. Projects include air emission testing from boilers, incinerators, furnaces, turbines, etc.
- Fluent in EPA Title 40 regulations.
- Expertise in 40 CFR 60, Appendix A&B testing and analysis procedures.
- Participant of Predictive Emission Monitoring Systems (PEMS) development of neural networks as Alternative Monitoring Systems.

Appendix F - Related Correspondence
MDNR Pre-test Protocol



PROPOSED TEST PLAN

Submitted to: MO Dept. of Natural Resources,
Air Pollution Control Program, Enforcement Section
P.O. Box 176, Jefferson City, MO 65102

Date Submitted: _____

Attention: Peter Yronwode

Proposed Test Date: December 3-6, 2002

1.) FACILITY INFORMATION:

Name: Doe Run Company		
Address: : 881 MAIN ST.		
City : Herculaneum	State: MO	Zip: : 63048
Name & title of Contact Person: Rusty Keller		
Phone No. of Contact Person: (636) 933-3097	Fax No.: (636) 933-3150	

2.) AIR POLLUTION SOURCE TO BE TESTED:

Type of Facility/Source: Primary Lead Smelter and Refinery		
Permit #	FIPS/Plant ID: : 099 / 0003	PORT #
Address/Location:		
Address/Location: North on Hwy 55 Hwy to Herculaneum exit {Next exit past Festus, MO and approx. 30 mi. South of St. Louis, MO}. Come off the Overpass and turn Rt. {East}. Go		
second Stoplight and turn left on "Old Hwy 21". Travel to top of Hill and turn Rt.. Travel		
over the Joachim bridge and make first Right. Follow Road to Plant.		
Reason for Test:	Condition of Permit	Consent Agreement
<input checked="" type="checkbox"/>	Administrative Order	
<input type="checkbox"/>	Other (specify)	

3.) TESTING FIRM INFORMATION:

Name of Firm: White Star Environmental		
Address: P.O. Box 238		
City Olive Branch	State: MS	Zip: 38654
Name & title of Contact Person: Joe Sewell		
Phone No. of Contact Person: (662) 893-3063	Fax No.: (662) 895-1651	
Number of employees of firm:		5
No. of employees actually engaged in air pollution source testing:		4
Organizational chart with names & title of personnel: (please attach)		

3.) TESTING FIRM INFORMATION: (cont.)

Location & description of laboratory facilities:

American Interplex; Little Rock, AR performing lead analysis

White Star Environmental performing particulate matter analysis

Subcontractor(s) utilized by firm for source testing activities: None

Number of air pollution sources previously tested by firm: 1000 +

Sources tested by firm in Missouri in past 3 years (source, test, date): 25

Doe Run – Glover, MO

Univ. of Missouri – Columbia, MO

4.) PERFORMANCE TEST INFORMATION:

Pollutant		No. of Sampling Points	Total Time per Test Run	No. of Test Runs	Test Method to be Used
1.	PM/Pb – #7 Blast Furnace Bldg BH	30	60 min	3	Reference Method 12
2.	PM/Pb – #8 Refinery Process Kettles	16	60 min	3	Reference Method 12
3.	PM/Pb – #9 Refiner Bldg	30	60 min	3	Reference Method 12
4.	PM/Pb – Main Stack	8	60 min	3	Reference Method 12
5.					
6.					
7.					
8.					
9.					
10.					
11.					
12.					

5. GENERAL**A. Sampling Equipment Information:**

The manufacturer and model of the sampling equipment to be used by the tester for the performance tests, along with a description of any equipment which may differ from that required by the specified method(s).

PM testing: Nutech Model 2010A Sampling Console

B. Test Procedures:

A description of any test procedures to be used in the conduct of the performance tests which may differ from the specified method(s).

Due to horizontal and large ducts, tester may utilize in-stack filter.

NOTE: Deviations from EPA test methods observed during test procedures will not necessarily be corrected by agency observer and could result in agency rejection of test results.

C. Analytical Procedures:

A description of any analytical procedures which differ from the specified method(s).

None

D. Data Sheets:

A sample of all field data sheets which do not provide the data shown on the example sheets in 40 CFR 60 for the specified method(s). (As previously submitted)

E. Air Pollution Control Equipment: (#7 Baghouse)

Types and manufacturers of all control equipment:

EIGHT (8) 1917 TA-SB Model 144, Series 6P, Wheelabrator Modular Jet III Continuous

Automatic Pulse Type Dust Collectors (in an 8 X 1 arrangement) [S/N 20-4495C]

Design or guarantee efficiency: 0.022 gr/ dry standard ft³

Design gas volume at full load (acfm): 300,000

Design pressure drop: 6" W.G.

Maintenance schedule and method of record keeping: Per 1997 Missouri SIP Agreement

E. Air Pollution Control Equipment: (#8 Baghouse)

Types and manufacturers of all control equipment:

TWO (2) 1917 TA-SB Model 144, Series 6P, Wheelabrator Modular Jet III ContinuousAutomatic Pulse Type Dust Collectors (in an 2 X 1 arrangement) [S/N 20-4495A]Design or guarantee efficiency: 0.022 gr. / Standard dry ft.³Design gas volume at full load (acfm): 90,000Design pressure drop: 6" W.G.

E. Air Pollution Control Equipment: (#9 Baghouse)

Types and manufacturers of all control equipment:

FIVE (5) 1917 TA-SB Model 144, Series 6P, Wheelabrator Modular Jet III ContinuousAutomatic Pulse Type Dust Collectors (in an 5 X 1 arrangement) [S/N 20-4495B]Design or guarantee efficiency: 0.022 gr. / standard ft.³Design gas volume at full load (acfm): 250,000Design pressure drop: 6" W.G.

E. Air Pollution Control Equipment: (Main Stack)

(5E)

ITEM #	Process ⁽¹⁾ Name	Control Device	Gas Volume ⁽²⁾	Percent of Total
1a ⁽³⁾	Sinter Machine	#3 Baghouse	300-350,000 ACFM @ 290°F	26.3
1b ⁽³⁾	Acid Plant	ESP; Acid Plant	55,000 ACFM @ 175°F	4.8
1c ⁽³⁾	Misc. transfers; Return Bin	South End Baghouse	25,000 ACFM @ ambient+5°F	2.2
1d ⁽³⁾	Mixing Drum	Mixing Drum Baghouse	12,000 ACFM @ ambient +5°F	1.1
1e ⁽³⁾	Claw Breaker; Ross Rolls; Corrugated Rolls; and Euromag	Crusher Baghouse	45,000 ACFM @ 190°F	3.9
1f ⁽³⁾	Cooler	Cooler Baghouse	110,000 ACFM @ 200°F	9.6
1g ⁽³⁾	Smooth Rolls	Smooth Rolls Baghouse	15,000 ACFM @ ambient +10°F	1.3
2	Blast Furnaces	#5 Baghouse	500-550,000 ACFM @ 170°F	43.8
3	Dross Plant	Dross Furnace Baghouse	80,000 ACFM @ ambient +10°F	7
-	Main Stack Total (4)	- All Sources	1,130,000 ACFM @ 190°F	100

(1) Each Process is a portion contributing to the main stack.

(2) Estimated flow rate based on equipment design specifications.

(3) Equipment item numbers 1a thru 1g are Sinter Plant related.

(4) Actual total main stack flow is expected to be somewhat lower than the listed as dictated by the specific needs of each process.

#3 Baghouse

Manufacturer: Wheelabrator Frye

Model:

S/N: Equip. #162-300

Design efficiency: 99.5%

Design flow acfm: 300,000 - 350,000

Design Pressure Drop: 8" W.C. Normal

ESP

Manufacturer: WHEELABRATOR

Model: (1) 24/33/5X8/12" HARDE Model 35032

S/N: Contract S/N 3559, DRC equip. #150-525

Design efficiency: 0.03GR/SDCF all fields, 0.06GR/SDCF w/1 field de-energized

Design flow acfm: 95,283 Max.

Design Pressure Drop: +/- 20 W.G. @ 550F continuous, 05" @ 600F Std. Oper.

Acid Plant Control for SO₂

Manufacturer: CHEMICO

Model:

S/N: equip. # 161-XXX

Design efficiency: {Scrubbers provide additional particulate capture to ESP}

Design flow acfm:

Design Pressure Drop:

South End Baghouse

Manufacturer: WHEELABRATOR

Model: #2614 RA-SB Model 120 JET III DUST COLLECTOR

S/N: 20-3260, equip. #150-610

Design efficiency: 99.5%

Design flow acfm: 24,000 @ 70F Max Temp. 300F

Design Pressure Drop: 5" W.G.

Mixing Drum Baghouse

Manufacturer: Research - Cottrell, Flex Kleen Corp. (1993)

Model: 120-WXTC-196 (III)

S/N: equip. #150-176

Design efficiency: 99.5%

Design flow acfm: 12,000

Design Pressure Drop: +/-30" W.G., -15" W.G. Oper. Press.

Crusher Baghouse

Manufacturer: Research Cottrell, FLEX-KLEEN Corp.

Model: #120-WMWC-660 (III)

S/N: PO# A-794926, equip. #150-347

Design efficiency: 99.6%

Design flow acfm: 40,100

Design Pressure Drop: +/- 20" W.G., 6"-8" Normal

Cooler Baghouse

Manufacturer: Research Cottrell, FLEX-KLEEN Corp.

Model: BG89125-R2 Model#120-WXWC-1944 (III)

S/N: P.O.#A-794934, equip. #150-349

Design efficiency: 99.6%

Design flow acfm: 131,600

Design Pressure Drop: +/- 20" W.G., 6"-8" Normal

CV22 Baghouse

Manufacturer: Custom Systems

Model: TD64-08

S/N: P.O.#A-201444-25T, equip. #150-349

Design efficiency: 99.5%

Design flow acfm: 3,140

Design Pressure Drop: +/- 20" W.G., 3"-6" Normal

76" Smooth Rolls Baghouse

Manufacturer: Micro-Pulsaire

Model:

S/N: equip #155-515

Design efficiency: 99.5% (0.007 gr/cf)

Design flow acfm: 15,000

Design Pressure Drop: +/- 20" W.C., 6" Normal

#5 Baghouse

Manufacturer: Wheelabrator - Frye Inc.

Model: #1624 Model #264 series 8

S/N: equip. #162-500

Design efficiency:

Design flow acfm: 550,000

Design Pressure Drop: 8" W.C.

Dross Furnace Baghouse

Manufacturer: Amerex

Model:

S/N: equip. #153-440

Design efficiency: 99.7%

Design flow acfm: 80,000

Design Pressure Drop: 8" W.C.

6. SPECIFIC Emission Source Process/Operation (#7 Baghouse)

Provide a full description of the process/operation being tested for air emissions, to include:

A. Characterization of plant/equipment/process:

The #7 baghouse ventilates the combined Blast Furnace and Dross Plant building fugitives. Two blast furnaces are present at the facility. The furnaces are water-jacketed to within 5 feet of the charge floor, and above that, they are lined with fire-clay brick. Both are equipped with center line offtakes for their process gas streams to a separate #5 baghouse and Main Stack. The furnaces are fed w/ coke & sinter via a shuttle conveyor system and are ventilated by a separate Dross furnace baghouse and Main Stack. Bullion is decopperized in the Dross Plant portion of the building in 4-250 ton kettles that are vented to the #5 baghouse by use of kettle hoods.

B. Manufacturer, model & serial numbers of all major components:

Blast Furnaces = St. Joe Lead Co.; N.A. (1965)

C. Rated process/production capacity:

Blast Furnace = 73 concentrate T/Hr @ roughly 75%Pb = roughly 55 Lead T/Hr/2fcs.
110 {50%Pb} Lead bearing material T/Hr/2 fce's, 55 Lead material T/Hr/per one furnace.
27.75 Tons of bullion / Hr / furnace X roughly 95% Pb = 26.4 Tons Pb / Hr
Dross Plant = 47 lead bullion Tons / Hr

D. Normal process/production capacity:

Blast Furnace = 55 tons of sinter charge / Hr x 0.48%Pb = roughly 26 tons of Pb produced / Hr/fce

E. Nature and relative % of raw material input to process:

Blast Furnace = Sinter & Secondaries @ 43% to 50% Lead
Dross Plant = Molten Lead bullion @ roughly 95% Lead.

F. Product(s) (with relative % if more than one):

From the Blast Furnaces: Molten Lead Bullion @ roughly 95% lead
From the Dross Plant kettles: Molten Decopperized Lead @ roughly 99% Pb.

G. Type(s) of fuel:

Natural Gas & Petroleum Coke vented to #5 Baghouse & Main Stack

Consumption Rate:

Natural Gas: roughly 8.2 MCF/Hr
Petroleum Coke: roughly 4 T/Hr/fce

H. Normal operating schedule:

Normal operating schedule is 24 hours per day, 7 days per week, 12 months per year.

I. Process flow diagram: (please attach):

6. SPECIFIC Emission Source Process/Operation (#8 Baghouse)

Provide a full description of the process/operation being tested for air emissions, to include:

A. Characterization of plant/equipment/process:

The #8 baghouse filters air from the kettle hoods in the Refinery and the CV-10 Belt under the Stock Sinter Storage Hoppers. The Refinery is basically a batch process Where kettles are worked in batches of roughly 250 tons per batch before moving to another kettle to work the next step. CV-10 belt is used on an as needed basis.

B. Manufacturer, model & serial numbers of all major components:

Eleven 250-ton kettles
CV-10 belt conveyor

C. Rated process/production capacity:

Refinery Kettles: 163 tons of lead bullion / hour
CV-10 belt: 55 Sinter feed T/Hr/ fce

D. Normal process/production capacity:

Kettles at: 2.5 kettles/day, 26 Ton of lead cast/Hr
CV-10 belt: 40.49 Lead bearing material T/Hr

E. Nature and relative % of raw material input to process:

Molten Lead at roughly 99% Pb

F. Product(s) (with relative % if more than one):

Refined Lead metal @ 99.99% Pb.

G. Type(s) of fuel:

Natural gas heated,
*{On separate ventilation system}

Consumption Rate:

N/A

H. Normal operating schedule:

Seven (7) days per week, 24 hours / day, 365 days / Yr

I. Process flow diagram: (please attach):

6.) SPECIFIC Emission Source Process/Operation (#9 Baghouse)

Provide a full description of the process/operation being tested for air emissions, to include:

A. Characterization of plant/equipment/process:

The #9 Baghouse ventilates the Refinery building fugitives. Lead is pumped and laundered into the Refining department, which is equipped with eleven 250-ton kettles. Each kettle is heated by one gas-fired burner which is on a separate ventilation system. Lead is pumped through the sequential kettle series, culminating in delivery of refined lead to casting machines.

B. Manufacturer, model & serial numbers of all major components:

Eleven 250-ton kettles

C. Rated process/production capacity:

Refinery Kettles: 163 tons of lead bullion / hour

D. Normal process/production capacity:

Kettles at: 2.5 kettles/day, 26 Ton of lead cast/Hr

E. Nature and relative % of raw material input to process:

Molten Lead at roughly 99% Pb

F. Product(s) (with relative % if more than one):

Refined Lead metal @ 99.99% Pb

G. Type(s) of fuel:

Natural gas ventilated by separate system

Consumption Rate:

NA

H. Normal operating schedule:

Seven (7) days per week, 24 hours / day, 365 days / Yr

I. Process flow diagram: (please attach):

6.) SPECIFIC Emission Source Process/Operation (Main Stack)

Provide a full description of the process/operation being tested for air emissions, to include:

- A. Characterization of plant/equipment/process:
SEE ADDITIONAL PAGES (6A)

- B. Manufacturer, model & serial numbers of all major components:
Sinter machine = McDowell-Wellman; F-S306-H (1964)
Blast Furnaces = St. Joe Lead Co.; N.A. (1965)

- C. Rated process/production capacity:
Sinter Plant = 270 tons of feed / Hr divide by 2 (returns) = roughly 135 tons of sinter / Hr
Blast Furnace = 73 concentrate T/Hr @ roughly 75% Pb = roughly 55 Lead T/Hr/2fcs.
110 {50%Pb} Lead bearing material T/Hr/2 fcs's, 55 Lead material T/Hr/per one furnace.
27.75 Tons of bullion / Hr / furnace X roughly 95% Pb = 26.4 Tons Pb / Hr

- D. Normal process/production capacity:
Sinter Plant = 90 tons of sinter / Hr x 0.48% Pb = roughly 43 tons of Pb in sinter / Hr
Blast Furnace = 55 tons of sinter charge / Hr/fce X 0.48% Pb = roughly 26 tons of Pb produced / Hr/fce

- E. Nature and relative % of raw material input to process:
Sinter Plant = Main Feed Mixture @ 43% to 50% Lead
Blast Furnace = Sinter & Secondaries @ 43% to 50% Lead

- F. Product(s) (with relative % if more than one):
Sinter Plant = Sinter @ 43% to 50% Lead
Blast Furnace = Lead Bullion @ roughly 95% lead

G. Type(s) of fuel: Natural Gas & Petroleum coke	Consumption Rate: Petroleum Coke: Roughly 4 T/Hr/fce Natural Gas: roughly 14 MCF/Hr
---	---

- H. Normal operating schedule:
Blast Furnace normal operating schedule is 24 hours per day, 7 days per week, 12 months per year.
Present Sinter Plant normal operating schedule is 24 hours per day, 5 days per week, 12 months per year.

- I. Process flow diagram: (please attach):

(6A)

The present normal mode of operation for the Herculaneum facility is to try to achieve maximum production through the use of one furnace operating 24 hours per day, 7 days per week, 52 weeks per year and to operate the Sinter Plant 24 hours per day, 5 days per week and 52 weeks per year. Although the throughput of individual unit processes may vary, the overall plant material throughput is relatively constant.

Exhaust air from the emission sources pass through control devices as listed in the above table before they enter the main stack. The concentration of particulate matter present in the main stack exhaust gas stream represents controlled emissions from all of the individual emission units that contribute to the main stack exhaust gas flow. Similarly, the concentration of lead and other metals in the main stack exhaust also reflects controlled emissions.

By definition, operation of the various emission units listed in the table is not continuous. Rather, it is an on-going sequence of batch-type unit operations that run repeatedly on a 24-hour per day, seven day per week basis. The only exception to this is when equipment is taken down for planned or unplanned maintenance. Due to their relatively small percentage of gas flow contributed to the total stack flow, when some of these processes are down, they have little influence on the total flow and total main stack emissions. The exception to this is when the sinter plant is down.

As shown in the table, the two exhaust gas streams that dominate the total air-flow to the main stack are from the sinter machine and the blast furnaces. These two emission units make up 70% of the total air-flow vented to the main stack. Nearly 27% of this is from the sinter machine operation and more than 44% from operation of the blast furnaces.

The 550ft. main stack is equipped with a test platform at an elevation that is 350 feet above grade. The platform, which surrounds the entire stack, consists of a 4 ft. wide walkway equipped with appropriate handrails and guarding for fall protection. Access to the test platform is via either a small electrically driven elevator or via safety ladder. There are standard 20 amp. Electrical outlets on this 350ft. level landing available for use during testing.

There are four 6-inch diameter (schedule 40) sample ports installed diametrically opposed in the stack at the platform elevation. The stack inside diameter at the elevation of the test ports is 32 feet 10 inches. The sample ports are located at a distance of 272 feet above the highest duct breaching to the stack. Based on the inside diameter of the stack at the test port elevation and the distance between the sample port elevation and the elevation of the stack breaching, the location of the sample ports are greater than 8 diameters and, therefore, meets the USEPA Method 1 specification for ideal stack base to the top, the taper is only 2.76 ft. per 100 ft. of stack height. This slight taper will not, therefore, have any significant effect on the air flow conditions within the stack.

Appendix G - Process Data

BLAST FURNACE FEED DATA SHEET

DATE: 12-3-02

BF# 2 SHIFT: Days NAME:

CHARGE		CHARGE TIME		NS		CHARGE		CHARGE TIME		NS				
CO	START	COKE	SINTER			CO	START	COKE	SINTER					
11	:	94	3.08	100	150	X	31	18	17:13	2914	245	3000	201	X
10	:	158	321	200	143	X	32	:	:	3000	234	3100	218	X
0	4:59	292	341	300	157	X	33	2	12:31	3102	227	3200	231	X
1	5:05	374	302	400	245	X	34	Ø	12:38	3196	223	3300	227	X
9	5:14	470	303	500	243	X	35	49	:	3290	213	3400	230	X
0	5:24	564	308	600	213	X	36	:	:	3384	212	3500	231	X
0	5:42	668	312	700	207	X	37	61	14:11	3478	146	3600	58	X
25	5:46	752	323	800	145	X	38	47	14:14	3572	752	3700	101	X
0	6:10	846	315	900	142	X	39	57	14:18	3666	148	3800	115	X
22	6:19	940	306	1000	154	X	40	67	14:23	3760	206	3900	142	X
13	6:43	1034	320	1100	201	X	41	66	14:27	3854	140	4000	136	X
13	6:53	1128	316	1200	219	X	42	52	14:30	3948	135	4100	108	X
Ø	7:17	1222	314	1300	255	X	43	11	15:20	4042	258	4200	403	X
9	7:26	1316	301	1400	244	X	44	:	:	4136	248	4300	211	X
Ø	7:36	1410	314	1500	331	X	45	115	15:34	4230	202	4400	239	X
Ø	7:51	1504	309	1600	311	X	46	103	15:39	4324	221	4500	253	X
0	8:10	1598	307	1700	308	X	47	:	:					
Ø	8:32	1692	325	1800	202	X	48	:	:					
Ø	8:45	1786	428	1900	148	X	49	:	:					
Ø	9:11	1880	309	2000	155	X	50	:	:					
Ø	9:26	1914	348	2100	207	X	51	:	:					
Ø	9:44	2068	236	2200	138	X	52	:	:					
10	10:13	2162	211	2300	133	X	53	:	:					
11	10:18	2256	208	2400	127	X	54	:	:					
Ø	10:24	2350	210	2500	148	X	55	:	:					
Ø	11:13	2444	214	2600	216	X	56	:	:					
Ø	11:20	2538	224	2673	700	X	57	:	:					
	:	2632	226	2700	75	X	58	:	:					
	11:59	2726	245	2800	138	X	59	:	:					
28	12:06	2820	257	2900	204	X	60	:	:					

BLAST FURNACE FEED DATA SHEET

DATE: 12-3-02

BF#

1

SHIFT: Days

NAME: J Adams

CHARGE		CHARGE TIME		NS		CHARGE		CHARGE TIME		NS
CO	START	COKE	SINTER			CO	START	COKE	SINTER	
X	:	1288		X	31	:				
X	9:58	1508		X	32	:				
X	10:07	1118		X	33	:				
X	10:31	1780		X	34	:				
X	10:35	1838	100	X	35	:				
X	10:44		300	X	36	:				
X	10:49	1948	300	X	37	:				
X	10:54	2058	400	X	38	:				
X	11:01	2168	500	X	39	:				
	:	2278	600	X	40	:				
	:	1443	1100	X	41	:				
	1:54	1773	1200	X	42	:				
	14:04	1883	1300	X	43	:				
97	14:51	1993	1400	X	44	:				
57	14:56	2052	1500	X	45	:				
9	15:10	2213	1600	X	46	:				
	:				47	:				
	:				48	:				
	:				49	:				
	:				50	:				
	:				51	:				
	:				52	:				
	:				53	:				
	:				54	:				
	:				55	:				
	:				56	:				
	:				57	:				
	:				58	:				
	:				59	:				
	:				60	:				

BF CHARGE INTERPRETATION.

COKE 94 $\xrightarrow{\text{TOTALIZER}} = \text{COUNTER}$ EACH DIGIT = 20 lbs.
3:08 \rightarrow TIME TO RUN CHARGE 3.08 minutes/seconds

SPINTER 100 $\xrightarrow{\text{TOTALIZER}} = \text{COUNTER}$ EACH DIGIT = 200 lbs.
1:50 \rightarrow TIME TO RUN CHARGE 1.50 minutes/seconds

12-3-02
#7 BARNHOUSE
STACK TEST - TRIBOFLW READINGS

TEST #1			TEST #2		TEST #3	
	TIME	TRIBOFLW	TIME	TRIBOFLW	TIME	TRIBOFLW
1	10:30	2.2	12:22	0.80	14:46	0.8
2	10:34	4.2	12:26	0.80	14:50	0.81
3	10:36	2.5	12:28	0.80	14:52	0.81
4	10:38	1.5	12:30	0.80	14:54	0.82
5	10:40	0.8	12:32	0.80	14:56	0.81
6	10:42	0.8	12:34	0.80	14:58	0.81
7	10:44	0.88	12:36	0.81	15:00	0.82
8	10:48	0.84	12:40	0.82	15:04	0.84
9	10:50	0.84	12:42	0.81	15:06	0.84
10	10:52	0.82	12:44	0.81	15:08	0.82
11	10:54	0.82	12:46	0.80	15:10	0.80
12	10:56	0.82	12:48	0.80	15:12	0.80
13	10:58	0.81	12:50	0.82	15:14	0.81
14	11:02	0.81	12:54	0.82	15:18	0.82
15	11:04	0.81	12:56	0.81	15:20	0.82
16	11:06	0.81	13:00	0.80	15:22	0.82
17	11:08	0.81	13:02	0.80	15:24	0.82
18	11:10	0.81	13:04	0.80	15:26	0.82
19	11:12	0.81	13:08	0.84	15:28	0.82
20	11:16	0.81	13:10	0.86	15:32	0.82
21	11:18	0.81	13:12	0.86	15:34	0.82
22	11:20	0.81	13:14	0.84	15:36	0.82
23	11:22	0.81	13:16	0.84	15:38	0.81
24	11:24	0.80	13:18	0.82	15:40	0.81
25	11:26	0.80	13:22	0.82	15:42	0.81
26	11:30	0.80	13:24	0.82	15:44	0.82
27	11:32	0.80	13:26	0.81	15:46	0.82
28	11:34	0.80	13:28	0.81	15:48	0.82
29	11:36	0.81	13:30	0.80	15:50	0.82
30	11:38	0.81			15:52	0.84
					15:54	0.83

IN PROCESS 12-4-0

DAY SHIFT
AND
CASTED

LOT CONTROL CARD

LOT NUMBER

7740

DROSS FURNACE KETTLE#:

DATE:

12-2-02

Vacuum zinc added? Yes ☐ No ☐Amount of new zinc added for desilverizing 0 lbsWas silver assay on pre-zinc sample high enough to make stubs? Yes ☐ No ☒If yes, how many stubs did you make? 0Was de-zinc kettle temperature between 950 and 1100 F Yes ☒ No ☐Based on the tail sample, was this kettle successfully dezincing? Yes ☒ No ☐What product are you making? DRF What pump? 19During casting, estimate amount of lead scrapped due to any reason. 4 Tons


What problems occurred while casting?

Work Order # Description

Completed

		Y	N
		Y	N
		Y	N
		Y	N

STAMPING:



7740

LOT CONTROL CARD

LOT NUMBER

7740

DROSS FURNACE KETTLE#:

DATE:

12-2-02

Vacuum zinc added? Yes ☐ No ☐Amount of new zinc added for desilverizing 0 lbsWas silver assay on pre-zinc sample high enough to make stubs? Yes ☐ No ☒If yes, how many stubs did you make? 0Was de-zinc kettle temperature between 950 and 1100 F Yes ☒ No ☐Based on the tail sample, was this kettle successfully dezincing? Yes ☒ No ☐What product are you making? DRI What pump? 19During casting, estimate amount of lead scrapped due to any reason. 4 Tons

What problems occurred while casting?

Work Order # Description

Completed

		Y	N
		Y	N
		Y	N
		Y	N

STAMPING:

7740

D7740

CORR

UP

IN PROCESS 12-4-02

DAY SHIFT

AND
CASTED

LOT CONTROL CARD

LOT NUMBER

7740

DROSS FURNACE KETTLE#:

DATE:


12-2-02

Vacuum zinc added? Yes ☐ No ☐Amount of new zinc added for desilverizing 0 lbsWas silver assay on pre-zinc sample high enough to make stubs? Yes ☐ No ☒If yes, how many stubs did you make? 0Was de-zinc kettle temperature between 950 and 1100 F Yes ☒ No ☐Based on the tail sample, was this kettle successfully dezincing? Yes ☒ No ☐What product are you making? ORI What pump? 19During casting, estimate amount of lead scrapped due to any reason. 4 Tons

What problems occurred while casting?

Work Order #	Description	Completed
		Y N
		Y N
		Y N
		Y N

STAMPING:



7740

12-4-03
TRIBOFLW READINGS
#9 BAGHOUSE

RUN #1			RUN #2		RUN #3	
	TIME	TRIBO READING	TIME	TRIBO READING	TIME	TRIBO READING
1	9:48	0.8	12:37	0.72	14:56	0.73
2	9:52	0.75	12:41	0.75	15:00	0.75
3	9:54	0.76	12:43	0.77	15:02	0.74
4	9:56	0.76	12:45	0.80	15:04	0.72
5	9:58	0.77	12:47	0.78	15:06	0.72
6	10:00	0.77	12:49	0.77	15:08	0.73
7	10:02	0.77	12:51	0.77	15:10	0.72
8	10:06	0.77	12:55	0.75	15:14	0.74
9	10:08	0.80	12:57	0.80	15:16	0.75
10	10:10	0.82	12:59	0.82	15:18	0.75
11	10:12	0.78	13:01	0.82	15:20	0.75
12	10:14	0.78	13:03	0.75	15:22	0.73
13	10:16	0.77	13:05	0.72	15:24	0.735
14	10:20	0.65	13:09	0.76	15:28	0.74
15	10:22	0.6	13:11	0.75	15:30	0.76
16	10:24	0.66	13:13	0.75	15:32	0.76
17	10:26	0.68	13:15	0.70	15:34	0.74
18	10:28	0.72	13:17	0.70	15:36	0.73
19	10:30	0.70	13:19	0.75	15:38	0.74
20	10:34	0.73	13:23	0.70	15:42	0.75
21	10:36	0.75	13:25	0.76	15:44	0.80
22	10:38	0.75	13:27	0.74	15:46	0.85
23	10:40	0.77	13:29	0.72	15:48	0.78
24	10:42	0.8	13:31	0.73	15:50	0.78
25	10:44	0.82	13:33	0.74	15:52	0.72
26	10:48	0.82	13:37	0.75	15:56	0.74
27	10:50	0.77	13:39	0.80	15:58	0.78
28	10:52	0.77	13:41	0.80	16:00	0.78
29	10:54	0.72	13:43	0.80	16:02	0.77
30	10:56	0.75	13:45	0.76	16:04	0.75

IN PROCESS 12-7-0
DAYSHIFT
#8
IN PROCESS 12-5
DAY SHIFT
AND CASTED

LOT CONTROL CARD

REFINERY

LOT NUMBER 7741

DROSS FURNACE KETTLE#: _____ DATE: 12-2-02 STARTED

Vacuum zinc added? Yes _____ No ☒

Amount of new zinc added for desilverizing 2056 lbs

Was silver assay on pre-zinc sample high enough to make stubs? Yes ☒ No ☒

If yes, how many stubs did you make? 16

Was de-zinc kettle temperature between 950 and 1100 F Yes _____ No _____

Based on the tail sample, was this kettle successfully dezincd? Yes _____ No _____

What product are you making? _____ What pump? _____

During casting, estimate amount of lead scrapped due to any reason. _____ Tons

What problems occurred while casting? _____

Work Order #	Description	Completed
_____	_____	Y N
_____	_____	Y N
_____	_____	Y N
_____	_____	Y N

STAMPING:

D 7741
D 7241 J. White
CORR

REFINERY

IN PROCESS 12-4-02
DANSHIFT

LOT CONTROL CARD

W8
IN PROCESS 12-5
DAY SHIFT
AND OASTED

LOT NUMBER

7742

DROSS FURNACE KETTLE#:

DATE:

12-3-02

Vacuum zinc added? Yes ☐ No ☒

Amount of new zinc added for desilverizing 4012 lbs

Was silver assay on pre-zinc sample high enough to make stubs? Yes ☒ No ☐

If yes, how many stubs did you make? 12

Was de-zinc kettle temperature between 950 and 1100 F Yes ☒ No ☐Based on the tail sample, was this kettle successfully dezincd? Yes ☒ No ☐

What product are you making? 1500A1 60 What pump?

During casting, estimate amount of lead scrapped due to any reason. Tons

What problems occurred while casting?

Work Order # Description

Completed

Y N

Y N

Y N

Y N

STAMPING:

7742
1500
1500

7742

BLAST FURNACE FEED DATA SHEET DATE: 12-5-02

BF# 1 SHIFT: Days NAME: S. Adams #8

CHARGE CO	START	CHARGE TIME		NS		CHARGE CO	START	CHARGE TIME		NS	
		COKE	SINTER					COKE	SINTER		
129	5:09	105	100 352	X	31	220	:	3325	3200 55	X	
131	5:18	210	300 351	X	32	233	:	3478	3300 117	X	
239	5:47	315	300 259	X	33	233	:	3551	3400 136	X	
150	5:55	420	400 352	X	34	320	:	3683	3500 140	X	
228	6:42	525	500 232	X	35	:	:				
300	6:49	1630	1600 352	X	36	:	:				
187	7:52	733	700 251	X	37	:	:				
135	8:00	830	800 217	X	38	:	:				
172	8:07	939	900 243	X	39	:	:				
199	8:21	1042	1000 243	X	40	:	:				
159	:	1143	1100 311	X	41	:	:				
137	8:40	1248	1200 310	X	42	:	:				
214	8:45	1351	1300 312	X	43	:	:				
:	:	1454	1400 248	X	44	:	:				
232	9:46	1557	1500 331	X	45	:	:				
183	10:09	1660	1600 453	X	46	:	:				
248	10:41	1933	1800 137	X	47	:	:				
242	10:49	2036	1900 143	X	48	:	:				
259	11:20	2139	2000 158	X	49	:	:				
278	11:27	2242	2100 134	X	50	:	:				
210	11:51	2345	2200 124	X	51	:	:				
224	12:10	2448	2300 123	X	52	:	:				
218	12:25	2551	2400 140	X	53	:	:				
254	12:43	2654	2500 133	X	54	:	:				
228	12:56	2757	2600 126	X	55	:	:				
318	1:15	2860	2700 123	X	56	:	:				
250	1:20	2963	2800 121	X	57	:	:				
:	:	3066	2900 116	X	58	:	:				
:	:	3169	3000 117	X	59	:	:				
270	2:25	3272	3100 118	X	60	:	:				

BLAST FURNACE FEED DATA SHEET

DATE: 12-5-02

BF#

2

SHIFT:

Day

NAME:

J Adams

28

CHARGE		20% chlt CHARGE TIME = 10 Ton		NS		CHARGE		CHARGE TIME		NS
CO	START	COKE	SINTER			CO	START	COKE	SINTER	
210	1:00	94	201	1000	214	31	:			
	:	188	210	200	32	32	:			
	:	282	211	300	325	33	:			
	:	376	204	400	341	34	:			
256	5:28	470	210	500	349	35	:			
210	5:36	564	211	600	319	36	:			
116	6:05	658	152	700	322	37	:			
123	6:14	752		800	346	38	:			
119	6:27	844	158	900	346	39	:			
112	6:34	940	210	1000	335	40	:			
116	7:00	1034	247	1100	345	41	:			
146	7:07	1128	331	1200	350	42	:			
208	7:31	1222	ENR	1300	350	43	:			
240	7:38					44	:			
	:					45	:			
	:					46	:			
	:					47	:			
	:					48	:			
	:					49	:			
	:					50	:			
	:					51	:			
	:					52	:			
	:					53	:			
	:					54	:			
	:					55	:			
	:					56	:			
	:					57	:			
	:					58	:			
	:					59	:			
	:					60	:			

BF CHARGE INTERPRETATION.

COKE 94 $\xrightarrow{\text{TOTALIZER}}$ = COUNTER EACH DIGIT = 20 lbs.
3:08 \rightarrow TIME TO RUN CHARGE 3.08 minutes/seconds

SINTER 100 $\xrightarrow{\text{TOTALIZER}}$ COUNTER EACH DIGIT = 200 lbs.
1:50 \rightarrow TIME TO RUN CHARGE 1.50 minutes/seconds

12-5-2002

#8 BARNHOUSE STACK TEST

TRIAD FLOW READINGS

TEST 1

	TIME	TRIAD FLOW
1	10:15	8.6
2	10:20	10.0
3	10:22	13.0
4	10:25	16.4
5	10:27	14.2
6	10:30	12.0
7	10:31	10.5
8	10:35	7.9
9	10:37	6.0
10	10:40	8.2
11	10:42	9.5
12	10:45	14.2
13	10:47	13.4
14	10:52	9.0
15	10:55	6.5
16	10:57	7.0
17	11:00	9.5
18	11:03	11.3
19	11:05	12.0
20	11:07	12.3
21	11:10	10.4
22	11:12	8.0
23	11:15	6.5
24	11:17	7.2
25		
26		
27		
28		
29		
30		

TEST 2

	TIME	TRIAD FLOW
	11:50	7.8
	11:55	3.6
	11:57	3.0
	12:00	3.8
	12:02	4.2
	12:05	8.2
	12:07	10.8
	12:10	10.5
	12:12	7.6
	12:15	5.2
	12:17	6.3
	12:20	7.6
	12:21	8.5
	12:26	9.2
	12:28	10.0
	12:31	7.5
	12:33	6.2
	12:38	6.0
	12:38	6.0
	12:41	8.0
	12:43	9.5
	12:48	10.0
	12:48	9.2
	12:51	8.5

TEST 3

	TIME	TRIAD FLOW
	13:50	8.6
	13:55	5.5
	13:57	4.2
	14:00	3.8
	14:02	3.2
	14:05	2.5
	14:07	1.8
	14:10	1.5
	14:12	1.8
	14:15	1.4
	14:17	1.4
	14:20	1.5
	14:23	1.5
	14:26	1.5
	14:28	1.5
	14:31	1.5
	14:33	1.6
	14:36	1.6
	14:38	1.6
	14:41	1.5
	14:43	1.5
	14:46	1.5
	14:48	1.6
	14:51	1.6